

J. H. KLEINFELDER & ASSOCIATES


HYDROGEOLOGIC ASSESSMENT  
POND NUMBER 1  
SOUTHERN CALIFORNIA CHEMICAL CO., INC.  
SANTA FE SPRINGS, CALIFORNIA

10-24-85 4A

**RECEIVED**

OCT 24 1985

SO. CALIF. CHEM. CO.



J. H. KLEINFELDER & ASSOCIATES  
GEOTECHNICAL & ENVIRONMENTAL CONSULTANTS • MATERIALS TESTING  
LAND & WATER RESOURCES  
VICTORIA CORNER BUSINESS PARK  
901 WEST VICTORIA STREET, SUITE G  
COMPTON, CALIFORNIA 90220  
(213) 638-9344

October 24, 1985

Southern California Chemical Co., Inc.  
8851 Dice Road  
Santa Fe Springs, California 90620

Attention: Ms. Tere King

Dear Ms. King:

Attached to this letter is our final report entitled "Hydrogeologic Assessment of Pond Number 1, Southern California Chemical Company, Santa Fe Springs, California". The report presents a summary of the field exploration, laboratory testing and analysis prepared during investigation.

We trust the information presented in the report meets your needs at this time. Should you have any questions regarding the report, please feel free to contact us at your convenience.

Very truly yours,

J. H. KLEINFELDER & ASSOCIATES

*Kenneth L. Durand*

Kenneth L. Durand  
Hydrogeologist

*Randolph C. Harris*

Randolph C. Harris  
Senior Hydrogeologist

KLD/RCH:gw

Attachment



HYDROGEOLOGIC ASSESSMENT OF POND NUMBER 1  
SOUTHERN CALIFORNIA CHEMICAL CO., INC.  
SANTA FE SPRINGS, CALIFORNIA

1.0 INTRODUCTION

This report summarizes the work and findings of the hydrogeologic assessment of Southern California Chemical Company's pond number 1. The purpose of this investigation was to determine if there has been leakage of pond number 1.

A site plan illustrating the facility is presented on plate 1 with the study area and location of pond number 1 illustrated on plate 2.

2.0 SCOPE OF WORK

The following scope of work was developed to determine if contamination of the soil or groundwater exists in the area of pond number 1 and, if contamination does exist, to determine its source. To that end, this work plan was developed to provide a technically sound, reasonable, and cost-effective approach to assessing the site.

2.1 Soil Borings/Sampling

A total of 11 soil borings were drilled in the vicinity of pond 1. The location of these borings are presented on plate 2. Depth of the borings ranged between 15 and 107 feet. Individual boring depths are presented in Table A and on the boring logs.

Due to artesian groundwater conditions, the use of hollowstem equipment beneath 45 feet was impossible. With the concurrence of the Regional Water Quality Control Board (RWQLB), the borings were drilled by the hollowstem auger method for the upper 45 feet. If the boring was deeper than 45 feet, then mud rotary equipment was used for the remainder of the hole. The augers, drill rod and drill bits were steam cleaned prior to use and between borings to minimize the potential for cross contamination. The drilling was performed by Datum Exploration under the observations of a J.H. Kleinfelder staff geologist who visually logged the borings and classified the soils. The boring logs are presented on Plate Nos. 4 through 14. Plate No. 3 illustrates the Unified Soils Classification System used to classify the soils encountered.

Soil samples were collected during the drilling operation at approximately 5 foot intervals in the unsaturated zone and then at stratigraphically significant intervals once groundwater was encountered. A modified Porter Sampler was used to collect samples. Soil samples were collected for both laboratory analysis and for visual classification of soil types. All retained soil samples were collected in brass sampling tubes, sealed with aluminum lined caps, labeled, and delivered to Brown and Caldwell Laboratories, Pasadena, California for chemical analysis, with the appropriate chain of custody form. Copies of the chain of custody forms are included in the Appendix.

## 2.2 Monitoring Well Construction/Development

Five of the soil test borings were completed as monitoring wells. Monitoring wells 4, 8 and 10 were constructed with 2-inch diameter PVC pipe and 0.020 inch machine slotted screen. Wells 4A and 9 were constructed with 4 -inch diameter PVC pipe and 0.020 inch machine slotted screen. The screened section annulus was packed with clean sand and a bentonite plug was placed above the sand pack. The remaining annulus was cemented from the plug up to the surface. No solvents or glues were used during the well construction. The details of each individual well completion are shown on each respective boring log.

Each well was finished with either an aluminum well head box with a moisture and tamper resistant lid or a locking steel cased well protector. The well head boxes are set 1 to 2 inches above ground level, with a finished cement apron to minimize the potential for entrance of surface fluids. A 3-foot high well protector was used on MW-4A to prevent damage due to truck traffic.

After installation the wells were developed with an air lift developing tool equipped with a foot valve to prevent the introduction of air into the formation. The wells were pumped until the water was relatively clear.

## 2.3 Water Sampling

All wells were measured for static water level prior to sampling. The wells were then purged and sampled using an air activated submersible pump (bladder pump) constructed of stainless steel and silicon. To minimize the potential for cross-contamination, the

pump and teflon sampling line were thoroughly decontaminated before sampling and between wells by the following procedure:

1. Exterior surface of sampling tubes are decontaminated by steam cleaning during withdrawal from every well.
2. Sample pump is disassembled and the used bladder removed.
3. All pump components are then steam cleaned and rinsed in distilled water.
4. Pump is reassembled with a new bladder installed.
5. Teflon sampler lines are pressure washed with 5 to 10 gallons of clean, hot water through direct connection to steam cleaner.
6. Five gallons of distilled water are then pumped through entire system.

Prior to sample collection, a minimum of five well volumes are purged from the well to permit collection of a representative groundwater sample from the aquifer penetrated.

#### 2.4 Laboratory Testing/Quality Control

Laboratory testing for this project consisted of analyzing 59 soil samples and 6 water samples. Soils were analyzed for the substances that have historically been used in the pond. These are listed in Table B. Water samples from monitoring well number 4 were analyzed for: 1) the parameters that characterize the suitability of the groundwater as a drinking water supply as specified in 40 CFR part 265 Appendix III; 2) the parameters that establish the groundwater quality as specified in 40 CFR part 265.92 (b) (a); 3)

the parameters used as indicators of groundwater contamination as specified in 40 CFR part 265.92 (b)(3); and 4) the compounds requested by Department of Health Services (DOHS) and the RWQCB in their letter dated December 11, 1984. These parameters are listed in Table C. Monitoring wells 4A, 8, 9 and 10 were analyzed for: 1) the parameters used as indicators of groundwater contamination as specified in 40 CFR part 265.92 (b)(3); and 2) substances detected above drinking water standards in monitoring well 4 during previous work. The testing was performed at Brown and Caldwell, Pasadena, California. The results of the laboratory testing were summarized and presented in Tables D through G of the Appendices. Individual test results are included in Appendixs A & B. All analysis was performed by procedures outlined in the 14th Edition of Standard Methods.

To monitor the precision and accuracy of the chemical data, the following quality assurance measures were employed:

1. Duplicate samples,
2. Split samples,
3. Trip blank testing,
4. Cross contamination testing.

Duplicate samples were taken at each sampling site. In the case of 40 ml VOA vials, four samples were obtained for each parameter as required in 40 CFR section 265.82 (b)(3). This ensures that if breakage or trouble with the testing equipment occurs, there is a backup sample to test. This also allows a recheck on results if there is an inconsistency or if confirmation of results is necessary.

Trip blank (distilled water) was included by the laboratory to monitor quality control during transportation and testing of the samples. Split samples were provided to both the RWCQB and Southern California Chemical Company. Comparison of the results for chromium in monitoring well 4, the major chemical of concern, demonstrate the relative consistency of the data. The Regional Board's laboratory consistently detected 520 ppm of total chromium. Brown and Caldwell detected 500 ppm of total chromium. Southern California Chemical Company's in-house laboratory detected 520 ppm of total chromium in the groundwater. This consistency demonstrates a high level of confidence in the results.

In an effort to ensure the precision and accuracy of the data, quality control measures were employed to both minimize and measure cross-contamination potential.

To minimize cross-contamination between field samplings, the pump and sample lines are purged by the procedure detailed in Section 2.3. The total volume of pump and lines is less than one-half gallon. The pumping results in 20 to 26 volumes of clean water being flushed through the system.

All samples were labeled during sampling and shipped refrigerated to Brown and Caldwell Laboratories, Pasadena, California. A chain of custody form was maintained for all samples taken. Copies of these forms are included in Appendix C.



### 3.0 GEOLOGY/HYDROGEOLOGY

#### 3.1 Geology

Southern California Chemical Company's Santa Fe Springs facility is located in Section 31 of Township 2 South, Range 11 west (San Bernardino Base meridian), within the Santa Fe Springs Plain area of the coastal plain of Los Angeles County, California. The Santa Fe Springs Plains is a low, slightly rolling topographic feature that has been warped by the Santa Fe Springs - Coyote Hills anticlinal system. These plains dip gently both to the northeast toward Whittier and to the southwest toward the Downey Plains, with an elevation difference that ranges between 175 and 200 feet above sea level.

The site is located on upper Pleistocene alluvium of the Lakewood Formation. The Lakewood formation unconformably overlies the lower Pleistocene San Pedro formation, the Pliocene Pico and Repetto formations, and the Miocene Puente formation. Beneath the site, only the Lakewood and the San Pedro formations contain fresh water bearing units (Plate 15).

#### 3.2 Hydrogeology

The site area is located on surface exposure of the Bellflower Aquiclude, a low permeability portion of the Lakewood formation. This late Pleistocene alluvial formation is approximately 15 to 20 feet thick and consists of clays, silts, silty clays and sandy clays at this location. The Gage Aquifer underlies this and is approximately 15 to 20 feet thick, consisting of fine to medium sands area. Under the Southern California Chemical site the Gage Aquifer is dry. The literature (2) places the bottom of the Gage Aquifer at approximately 50 feet beneath the surface. On-site borings indicated

that the bottom of the Gage is actually at approximately 30 to 35 feet. All the borings drilled on site encountered a clay to silty clay layer beneath the Gage. This is most likely the top of the uppermost aquiclude of the San Pedro Formation. This aquiclude is approximately 15 to 20 feet thick and serves to separate the Gage Aquifer from the Jefferson Aquifer. The Jefferson Aquifer underlies this aquiclude and is the uppermost aquifer beneath the site. All water samples were obtained from this aquifer. The transmissivity of this aquifer is on the order of 40,000 gallons per day per foot (2) beneath the site. Based on an assumed aquifer thickness of 50 feet and an error factor of  $1 \times 10'$ , a permeability range of 8000 to 80 gal/day/ft<sup>2</sup> can be expected.

The general regional flow of groundwater in the area is to the south to southwest (3, 9). The water levels measured in the monitoring wells indicate a site-specific flow to the south-southwest. Plate 16 illustrates the approximate water level contours and flow direction based on the data generated during this study.

#### 4.0 HISTORY OF POND 1

Pond number 1 was a 36,000 gallon wastewater treatment pond located approximately in the center of the facility. The pond was constructed in 1975 of 6" reinforced concrete. Company records indicate that the contents of the pond varied only slightly during the ten years of operation. Plate 17 presents the reactions, quantities and frequencies of chemicals used in pond 1. Sludge from this pond was periodically removed and disposed of in an approved facility. Representative hazardous waste monitoring of this sludge

removed during the period December 1981 to present are included in Appendix D. Reviewing the chemical reactions as outlined in plate 17 indicate that the pH of the pond was maintained above 6. The only exception to this was during the period between January 1983 and August 1984, chromic-sulfuric acid was added just prior ( $\frac{1}{2}$  to 1 hour) to sludge removal. This mixing of pond sludge and acid was done to neutralize the acid so it would be accepted by the Class I landfill.

In August 1985 use of the pond was discontinued. After the pond was drained and cleaned, there were no visible signs of leakage, or of chemical degradation of the concrete. This was expected since the high pH of the pond precipitated gypsum which reinforced the pond's seal.

## 5.0 CHEMICAL DATA

### 5.1 Groundwater Samples

Groundwater samples were collected from monitoring wells 4A, 8, 9 and 10 between July 24, 1985 and August 30, 1985. Representatives of the Regional Board and Southern California Chemical Company were present during sampling and were provided split samples when requested.

Analyses of the water from the five monitoring wells are presented in Tables F and G. Chromium, cadmium and nitrates are below drinking water standards for all wells except MW 4. Monitoring well 4 contains levels up to 0.78 mg/l of cadmium, 500 mg/l of chromium, and 81 mg/l of nitrate ( $\text{NO}_3$ ). Specific conductance of all the wells except MW 4A are above drinking water standards. This, however, is not uncommon

for shallow aquifers in the Los Angeles County. TOC was detected at levels up to 440 mg/l in MW 10 and up to 210 mg/l in MW 9. These are above background for this area. In addition, organic chemicals were detected in MW 4 at levels up to 10 mg/l. The laboratory data reports are indicated in Appendix.

## 5.2 Soil Samples

59 soil samples from the pond area were analyzed for pH, cadmium, chromium, copper, zinc, nickel, chloride, sulfate, ammonia nitrogen and carbonate. Thirty of these samples were analyzed by Brown & Caldwell Laboratories. These are presented on Tables D and E. The other 29 samples were analyzed by Southern California Chemical's in-house lab. Soil concentrations are presented on plates 18 through 23.

### Chromium

Chromium values on site range from 30,000 mg/kg to 3.7 (Plate 18). The high values were detected in the old tank area with values up to 30,000 mg/kg at 5 feet, decreasing to 3,000 mg/kg at 35 feet. Beneath the pond, values increase from the 50 mg/kg range at 10 feet to 2,000 mg/kg at 30 feet.

### pH

Values for pH ranged between 3.1 and 8.7 in the study area (Plate 19). Values beneath the pond were significantly lower than levels detected around the pond. This is significant since the pH levels of the product in the pond were between 6 and 13.

### Copper

Copper was detected at levels between 13,000 mg/kg and 25 mg/kg in the study area. The higher levels (above 1,000 mg/kg) were detected in the old tank area. Beneath the pond values ranged between 100 and 500 mg/l (Plate 20).

### Chloride

Chloride levels on site ranged between 420 mg/kg and 5,500 mg/kg. The highest level was detected in slant boring 2, 35 feet beneath the pond. Chloride in the old tank area ranged between 1,100 and 1,800 mg/kg (Plate 21).

### Other Substances

Cadmium, zinc, nickel, sulfate, ammonia nitrogen, and carbonate were analyzed in selective samples. Except for the 15-foot sample of Boring 6, no significant levels of these substances were detected.

## 6.0 DISCUSSION

### 6.1 Water Quality

As part of Phase I of this study, seven monitoring wells were completed and sampled for all the RCRA requirements. Of all the monitoring wells, only one (MW4) had levels above the Primary Drinking Water Standards. Chromium, cadmium, and nitrates were detected in MW4. A second phase of investigation was undertaken to determine the horizontal and vertical extent of the chemical constituents in the groundwater. Four additional monitoring wells (MW4A, 8, 9, and

10) were installed around the wastewater pond. After sampling these new wells, it was determined that none of the substances detected above the Primary Drinking Water Standards in MW4 during Phase I exist above the standards in these new wells. At present therefore, the chemical compounds have only been identified in MW4. If it is assumed that the chemical constituent plume extends up to each of the nearest monitoring wells, the contamination plume is at the most 80 to 100 feet long (north - south) by 40 to 50 wide (east - west) and is contained within the site boundaries. In addition, the plume was not detected in MW4A, which was screened at a deeper interval (87 to 107 feet) than MW 4 (45 to 75 feet). The top of the confined aquifer beneath the pond is at 55 feet. Assuming the chemical constituents extend vertically to just above the 87-foot level, the maximum plume thickness at MW4 is approximately 32 feet.

During Phase I sampling, the Los Angeles Regional Water Quality Control Board (RWQCB) was provided split samples for analysis. In addition to the RCRA substances, as outlined in the original study plan, the RWQCB analyzed for organic chemicals. The RWQCB analysis indicated the presence of Toluene, Xylene, Ethylbenzene and a number of other organic compounds in the groundwater beneath the site. Southern California Chemical then resampled and verified these analyses.

Once the maximum probable extent of the plume had been approximated, the source needed to be identified. The source of the organics has not yet been identified. Southern California Chemical Company is solely an inorganic chemical manufacturer. Company records

indicate that organic chemicals have never been used on site, even in laboratory quantities. It should be noted that eight of the surrounding neighbors are organic chemical plants. It is not known how organic compounds have migrated into the water sampled at MW4.

Review of company records indicates that the source of chromium in the water could be the result of one of three possibilities: the first is surface spillage before the plant was paved; the second is the wastewater pond; and the third is an underground storage tank that was removed 11-15 years previously and that apparently to have leaked. As will be discussed in the next two sections, the possibility that surface spillage was the source is still unknown. The waste water pond as the source is highly unlikely. The most likely source is the old tank area.

## 6.2 Soil Quality

In order to determine the source of the contaminated groundwater, an additional set of soil borings were drilled. Two of these borings (B1 and B2) were slant drilled adjacent to and under the pond. The other four (B3, B4, B5 and B6) were drilled vertically to attempt to locate the site of the old underground tank. Company records indicated that this tank was located 40 to 50 feet to the northeast of pond number 1. This tank contained a chrome etching solution which was a chrome, copper, chloride, ammonia, nitrogen and sulfate mixture and was low in pH. From the borings and the monitoring wells (MW4, 4A, 8, 9 and 10), selected soil samples were analyzed. The results of these analyses are presented in Tables D and E and illustrated on plates 18 to 23.

Review of the data in Tables D and E indicate elevated levels of chromium in the shallow soils at the site of the old tank. These levels decrease with depth, which suggests a surface or near surface source existed/exists in this area. The data from borings B1 and B2 beneath the pond indicate that the chromium levels at the 10 foot depth are relatively low but the levels increase with depth. This suggests that the chromium is not coming from a surface source in this area, but is migrating under the pond from an outside source.

Analysis of the pH data from Table 19 provides a second and more convincing indicator that the chromium is apparently migrating under the pond from a source outside of the pond area. As discussed in Section 4.0, the liquid in the pond was maintained between pH 6 and 13. The pH values of the soil from borings B1 and B2 under the pond are neutral or acidic (pH 8-3.9) at shallow depths, and decrease to pH 5.5 to 3.3 with increasing depth. This indicates that the low pH source is most likely migrating laterally under the pond from an outside source.

The pH of the old chromium tank was in the range of 1 to 3, which explains the low pH values in the tank area.

Copper is another element which, like chromium and pH, has higher levels in the old tank area and low levels at shallow depths beneath the pond. The levels increase with depth. This also suggests that the old tank area is the probable source of the chemical constituents beneath the pond.

Further demonstration of this theory is provided by nitrogen (as ammonia) and sulfate. Both of these chemicals were used in the



wastewater pond. Both are only found at elevated levels in the tank area (in particular, in B6). Both were detected at only low levels beneath the pond.

Chloride is the only chemical that has higher values in the soils beneath the pond than in the tank area. This is to be expected since chloride is the most soluble and conservative of the substances that were stored in the old tank, and would have been easily displaced in the near surface by soil moisture migration once the source was removed.

### 6.3 Vadose-Zone Transport

Migration of contaminants from the old tank area to under the pond area likely occurred as unsaturated-zone migration, which is dissimilar to the forces governing saturated-zone migration. Capillary forces and gravitational attractions predominate, resulting in a downward migration except in those areas where fine-grained materials (silts and clays) overlie clean sands. In this case, capillary forces resist the vertical drainage from the fine-grained material until such time as the field capacity of the material is exceeded, at which time a "break through" of fluid will migrate downward through the sand to form a perched layer at the sand base. This explains the observed presence of high levels of chromium in the fine-grained layers, low levels in the upper portions of the sand layer, and high levels at the base of the sand.

Carbonate material present in the silts and sands have reacted with acidic material in the seepage to sequentially precipitate copper, but not hexavalent chromium.<sup>11</sup>

## 7.0 CONCLUSIONS

The following general conclusions can be drawn from the foregoing data. Future studies may add to, and/or change these conclusions.

1. A confined aquifer exists beneath the site with a potentiometric surface between approximately 42 to 45 feet below ground level.
2. The general direction of groundwater flow is to the south-southwest.
3. Relatively low permeability soils were encountered from the surface to approximately 10 feet below ground surface. A second low permeability zone was encountered at approximately 25 to 50 feet below ground surface.
4. Based on the chemical data presented in this report, there is no evidence that leakage of pond number 1 has occurred.
5. The elevated levels of chrome and copper detected under the pond appear to have been due to leakage from the old tank area.
6. Waste from the old tank area migrated vertically through the vadose zone to the base of the 30 foot sand and then laterally under the pond.

## 8.0 RECOMMENDATIONS

1. Immediately implement groundwater extraction to remove high levels of chromium and organics in the vicinity of MW 4.

2. Promptly implement the pilot study to determine the optimum treatment procedure for possible in site treatment of the soil in the old tank area.

## 9.0 REFERENCES

The references used in the preparation of this preliminary report include, but are not limited to, the following:

1. U.S.G.S. Topographic Map, Whittier Quadrangle, 1981.
2. DWR Bulletin 104, Appendix A.
3. Division of Water Rights, map, Location of Water Wells.
4. Watermaster Service Central Basin, Los Angeles County, July 1, 1981 - June 30, 1982.
5. Watermaster Service Central Basin, Los Angeles County, July 1, 1982 - June 30, 1983.
6. DWR Bulletin 8.
7. DWR Bulletin 63, Appendix A.
8. Report on TCE Investigation, Los Angeles Regional Water Quality Control Board, April 1980.
9. Coastal Plain Ground Water Contours, Shallow Aquifer, Los Angeles Flood Control District, map no. 2-H240, Fall 1975.
10. Southern California Chemical Company records.
11. Rouse and Pyrih, (1985) "International Conference on New Frontiers in Waste Management."

## 10.0 LIMITATIONS

The conclusions and recommendations in this report are based on:

1. The 11 test borings performed at this site.
2. The observations of our field personnel.
3. The results of laboratory tests performed by Brown and Caldwell Laboratories.
4. The results of the land survey conducted by Combs/Rodriguez & Associates Land Surveying.
5. Measurements of groundwater elevations in the five monitoring wells.
6. Referenced documents.

It is possible that variations in the soil or groundwater conditions could exist beyond the points explored in this investigation. Also, changes in the groundwater conditions found could occur at some time in the future due to variations in rainfall, temperature, regional water usage, or other factors. The services performed by J.H. Kleinfelder & Associates have been conducted in a manner consistent with the level of care and skill ordinarily exercised by members of our profession currently practicing under similar conditions in the Los Angeles County Area. No other warranty, expressed or implied, is made.

Respectfully submitted,

J.H. KLEINFELDER & ASSOCIATES

*Kenneth L. Durand*  
Kenneth L. Durand  
Hydrogeologist

*Randolph C. Harris*  
Randolph C. Harris  
Senior Hydrogeologist  
R.G. #3708

KLD:RCH:ga

Attachments

**TABLE A**  
**MONITORING WELL AND BORING DEPTHS**

<u>Boring Number</u>	<u>Depth (ft)</u>	<u>Soil Boring or Monitoring Well</u>	<u>Perforated Interval (ft)</u>
B1	50	Soil Boring	--
B2	40	Soil Boring	--
B3	15	Soil Boring	--
B4	30	Soil Boring	--
B5	30	Soil Boring	--
B6	30	Soil Boring	--
MW4	75	Monitoring Well	45 - 75
MW4A	107	Monitoring well	87 - 107
MW8	76	Monitoring Well	46 - 76
MW9	77	Monitoring Well	47 - 77
MW10	75	Monitoring Well	45 - 75

TABLE B

CHEMICALS USED IN POND NUMBER 1

Ammonium sulfate solution  
Sodium chloride solution  
Ferrous hydroxide solution  
Copper ammonium chloride solution  
Chromic-sulfuric acid solution \*  
Sodium sulfate solution  
Sulfuric acid solution  
Ammonium chloride  
Free ammonium  
Copper sulfide  
Iron sulfide  
Chrome sulfide  
Nickel sulfide  
Zinc sulfide  
Lead sulfide

NOTES: \* See discussion in Section 4.0 concerning Chromic-sulfuric acid solution.

TABLE C

## \* WATER ANALYSIS PERFORMED

Drinking Water Parameters	Parameters Establishing Groundwater Quality	Parameters Indicating Groundwater Contamination*
Arsenic	Chloride	**pH
Borium	Iron	**Specific Conductance
**Cadmium	Manganese	**TOC
**Chromium	Phenols	**TOX
Fluoride	Sodium	
Lead	Sulfate	
Mercury		
**Nitrate		
Selenium		
Silver		
Endrin		
Lindane		
Methoxyphlor		
Toxaphene		
2,4-D		
2,4,5-TP Silver		
Rodium		
Gross Alpha		
Coliform Bacteria		

Additional Analysis as required by DOHS & RWQCB

---

Ammonia  
Sulfides  
Hexavalent Chrome  
Nickel  
Zinc

NOTES: \* = Groundwater indicator parameters performed in quads  
 \*\* = Water analysis performed in Phase II study.

**TABLE D**  
**TABULATION OF SOIL DATA**  
(mg/kg)

<u>Boring #</u>	<u>Depth</u>	<u>pH</u>	<u>Cadmium</u>	<u>Chromium</u>	<u>Copper</u>	<u>Zinc</u>	<u>Nickel</u>	<u>Chloride</u>	<u>Sulfate</u>	<u>Ammonia Nitrogen</u>	<u>Carbonate</u>
B1	10	8.0	--	53	470	--	--	--	--	--	--
	15	7.0	--	13	130	--	--	--	--	--	--
	40	3.9	1.5	600	400	180	--	5100	20	29	ND
	50	5.5	8.0	280	160	95	--	2600	71	10	ND
B2	15	3.9	--	54	390	--	--	--	--	--	--
	20	3.9	--	440	230	--	--	--	--	--	--
	35	3.3	1.2	2000	250	120	--	5500	41	42	ND
	40	3.3	1.4	150	550	170	--	2900	45	11	ND
B3	5	8.1	--	420	1200	--	--	--	--	--	--
	15	6.3	ND 0.67	11	31	57	--	1100	110	23	ND
B4	5	4.6	--	10000	480	--	--	--	--	--	--
	10	4.0	ND 0.62	16000	820	92	--	--	--	--	--
	25	4.2	ND 0.61	550	1200	52	--	1400	450	25	ND
B5	5	8.7	--	85	230	--	--	--	--	--	--
	10	8.3	--	30	78	79	26	--	--	--	--
	15	4.8	--	3200	12000	--	--	1600	170	21	ND
	25	4.5	--	49	160	34	12	--	--	--	--
B6	5	4.5	--	3700	460	--	--	--	--	--	--
	15	3.6	--	5100	4100	430	240	1800	2000	500	ND
	25	4.2	--	1500	1400	43	98	--	--	--	--

Notes = Depth is in feet  
ND 0.67 = Not Detected at 0.67 mg/kg (ppm)



TABLE E  
TABULATION OF SOIL DATA  
(mg/kg)

<u>Boring #</u>	<u>Depth</u>	<u>pH</u>	<u>Cadmium</u>	<u>Chromium</u>	<u>Copper</u>	<u>Zinc</u>	<u>Nickel</u>	<u>Chloride</u>	<u>Sulfate</u>	<u>Ammonia Nitrogen</u>	<u>Carbonate</u>
4	10	--	--	16	37	52	21	--	--	--	--
	30	--	--	19	50	72	25	--	--	--	--
4A	10	4.9	--	14	410	110	31	--	--	--	--
	25	6.2	--	67	24	150	9.7	2700	79	29	ND
8	10	7.3	--	41	61	96	27	--	--	--	--
	25	8.5	--	37	94	54	ND 3.1	510	50	10	--
9	15	6.9	--	15	28	55	19	4800	67	8.4	ND
	25	7.4	--	4.3	18	29	4.6	--	--	--	--
10	10	8.3	--	31	89	100	28	--	--	--	--
	25	7.3	--	5.3	25	30	6.4	470	67	66	ND

NOTES: Depth is in feet beneath ground surface.  
ND 3.1 = Not Detected at 3.1 mg/kg (ppm).

**TABLE F**  
**TABULATION OF WATER DATA**  
(mg/l)


	MW4	MW4A	MW8	MW9	MW10
Cadmium	0.78	ND 0.01	ND 0.01	ND 0.01	ND 0.01
Chromium (Total)	500	ND 0.03	ND 0.03	ND 0.03	ND 0.03
Chromium (Hexavalent)	500	ND 0.5	ND 0.5	ND 0.5	ND 0.5
pH	6.3	6.8	6.6	6.4	6.8
Conductivity	6400	1500	2800	2200	2100
TOC	36	40	99	210	440
Nitrate as NO <sub>3</sub>	81	20	5.8	6.3	ND 0.44
as N	18	4.5	1.3	1.4	ND 0.10

NOTES: MW 4 was sampled March 1985 per RCRA requirements. A complete list of the substances analyzed are included in the phase 1 report. MW 4A, 8, 9 and 10 were sampled August 1985 for the substances that are above drinking water standards in the March sampling and for the groundwater indicator parameters.

TABLE G  
TABULATION OF WATER DATA  
(mg/l)

	<u>DOHS</u>	<u>MW 4</u>	<u>B &amp; C</u>
1,1 Dichloroethane	41		100
1, Dichloroethylene	52		100
Benzene	3.7		ND 50
Carbon Tetrachloride	--		ND 50
Chloroform	24		ND 50
Ethylbenzene	2100		3000
Methylene Chloride	93		100
Trichloroethylene	225		550
Toluene	4500		8300
trans-1, 2-Dichloroethylene	14		ND 50
Phenols	0.001		ND 50
Perchloroethylene	--		ND 50
1,2 dichloroethane	13		ND 50
Semi-quantified Xylene			10,000
O-xylene	1,100		
N-P-xylene	2,000		

NOTES: DOHS = Department of Health Services data  
B & C = Brown and Caldwell data



J.H. KLEINFELDER & ASSOCIATES  
 GEOTECHNICAL CONSULTANTS • MATERIALS TESTING

SOUTHERN CALIFORNIA CHEMICAL  
 SANTA FE SPRINGS, CA.

PROJECT NO. Q1014-2

SITE PLAN

PLATE

1

# EXPLANATION



WATER MONITORING WELL




EXPLORATORY BORING



EXPLORATORY BORING  
ARROW INDICATES DIRECTION  
BORING SLANTS

0 10 20  
FEET



J.H. KLEINFELDER & ASSOCIATES  
GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



SOUTHERN CALIFORNIA CHEMICAL  
SANTA FE SPRINGS, CA.

BORING/WELL LOCATIONS

PLATE

2

PREPARED BY: DATE:

CHECKED BY: DATE:

PROJECT NO. Q 1014-2

# UNIFIED SOIL CLASSIFICATION SYSTEM

MAJOR DIVISIONS		LTR	DESCRIPTION	MAJOR DIVISIONS		LTR	DESCRIPTION
COARSE GRAINED SOILS	GRAVEL AND GRAVELLY SOILS	GW	Well-graded gravels or gravel sand mixtures, little or no fines.	FINE GRAINED SOILS	SILTS AND CLAYS LL<50	ML	Inorganic silts and very fine sands, rock flour, silty or clayey fine sands or clayey silts with slight plasticity.
		GP	Poorly-graded gravels or gravel sand mixture, little or no fines.			CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays.
		GM	Silty gravels, gravel-sand-clay mixtures.			OL	Organic silts and organic silt-clays of low plasticity
		GC	Clayey gravels, gravel-sand-clay mixtures.			MH	Inorganic silts, micaceous or diatomaceous fine sandy or silty soils, elastic silts
	SAND AND SANDY SOILS	SW	Well-graded sands or gravelly sands, little or no fines.		SILTS AND CLAYS LL>50	CH	Inorganic clays of high plasticity, fat clays.
		SP	Poorly-graded sands or gravelly sands, little or no fines.			OH	Organic clays of medium to high plasticity.
		SM	Silty sands, sand-silt mixtures.			Pt	Peat and other highly organic soils.
		SC	Clayey sands, sand-clay mixtures.		HIGHLY ORGANIC SOILS		



Standard penetration split spoon sample



Modified California sampler



Shelby tube sample



Water level observed in boring

\* No recovery

NFWE No free water encountered

NOTE: The lines separating strata on the logs represent approximate boundaries only. The actual transition may be gradual. No warranty is provided as to the continuity of soil strata between borings. Logs represent the soil section observed at the boring location on the date of drilling only.

J.H. KLEINFELDER & ASSOCIATES  
GEO TECHNICAL CONSULTANTS • MATERIALS TESTING



## BORING LOG LEGEND


PREPARED BY: DATE:

CHECKED BY: DATE:

PROJECT NO.

PLATE

3



J.H. KLEINFELDER & ASSOCIATES  
GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



So. Calif. Chemical  
Santa Fe Springs, Ca.

PLATE


4

LOG of BORING MW-4

PREPARED BY: JF DATE: 5/85

CHECKED BY: DATE:

PROJECT NO. Q-1014-1



J.H. KLEINFELDER & ASSOCIATES  
GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



So. Calif. Chemical  
Santa Fe Springs, Ca.

PLATE

4

## LOG of BORING MW-4


PREPARED BY: JF DATE: 5/85

CHECKED BY: DATE:

PROJECT NO. Q-1014-1



DEPTH (feet)

	Blow Count	Sample	USCS	Description	Well Const.
60	88/5	8	SM	silty sand, fine, brown, v.dense, wet  sand pack →  slotted PVC casing →	
65					
70					
75				Boring terminated at 75 ft (El.75') Date of drilling 1-16-85 Elevation of well head 149.76' Materials logged by J.Friedman	

J.H. KLEINFELDER & ASSOCIATES  
GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



So. Calif. Chemical  
Santa Fe Springs, Ca.

PLATE

4

LOG of BORING MW-4

PREPARED BY: JF DATE: 5/85

CHECKED BY: DATE:

PROJECT NO. Q-1014-1

DEPTH (feet)	Blow Count	Sample	USCS	Description	Well Const.
35	80	35	ML/CL	Clayey silt/silty clay, dark brown, very stiff-hard, very moist	
40					
45	80	45			
50				Blank PVC casing	
55				Concrete grout	
60					
65					

J.H. KLEINFELDER & ASSOCIATES  
GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



Southern California Chemical

LOG of BORING MW-4A

PLATE

5

PREPARED BY: DATE:

CHECKED BY: DATE:

PROJECT NO. Q-1014-2

DEPTH (feet)	Blow Count	Sample	USCS	Description	Well Const.
0				6" Concrete Lock well cap PVC cap	
5	10	5	ML	Silt with fine sand, brown, stiff, moist	
10	23	10	ML/SP	Sandy silt/silty sand, brown, dense, moist	
15	41	15	SP	Sand: medium - coarse sand, brown, very dense, dry	
				Blank PVC casing Concrete grout	
20	66	20	SP	Sand, coarse to medium sand, light brown, very dense, dry-damp	
25	98+	25	SP	Medium-coarse sand, light brown-tan, very dense, dry-moist	
30					

J.H. KLEINFELDER & ASSOCIATES  
GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



Southern California Chemical

PLATE

## LOG of BORING MW-4A

5


PREPARED BY:

DATE:

CHECKED BY:

DATE:

PROJECT NO. Q-1014-2

DEPTH (feet)	Blow Count	Sample	USCS	Description	Well Const.	
100	82	100	ML	Silt & very fine sand, brown, very dense, wet		
				Slotted PVC casing		
105		105	ML	Silt, occasional clast 72cm, brown, dense, damp		
				Sand pack		
110	75	110	SM/SP	Silty sand, brown, very dense, wet		
	75			Sand, fine-medium, very dense, wet		
				Boring terminated at 110'. Date of drilling 7-10-85. Materials logged by Ken Durand.		

J.H. KLEINFELDER & ASSOCIATES  
 GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



Southern California Chemical

LOG of BORING MW-4A

PREPARED BY: DATE:

CHECKED BY: DATE:

PROJECT NO. Q-1014-2

PLATE

5

DEPTH (feet)	Blow Count	Sample	USCS	Description	Well Const.
70					
				Concrete grout	
75					
				Bentonite	
80	53+	80	SP	Sand, fine, brown, dense, wet	
85					
90	98	88	SP	Sand, fine-medium, gray, very dense, wet	
				Slotted PVC casing	
95					
				Sand pack	
100					

J.H. KLEINFELDER & ASSOCIATES   
 GEOTECHNICAL CONSULTANTS • MATERIALS TESTING

Southern California Chemical

PLATE


5

LOG of BORING MW-4A

PREPARED BY: DATE:

CHECKED BY: DATE:

PROJECT NO. Q-1014-2



J.H. KLEINFELDER & ASSOCIATES  
 GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



So. Cal. Chemical  
 SANTA FE SPRINGS, CALIF.


LOG of BORING MW-8

PLATE

6

PREPARED BY: \_\_\_\_\_ DATE: \_\_\_\_\_  
 CHECKED BY: \_\_\_\_\_ DATE: \_\_\_\_\_

PROJECT NO. 01014-2



J.H. KLEINFELDER & ASSOCIATES  
 GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



So. Chemical Co.

SANTA FE SPRINGS, CALIFORNIA

LOG of BORING MW-8

PLATE

6

PREPARED BY: DATE:

CHECKED BY: DATE:

PROJECT NO. Q1014-2

DEPTH (feet)	Blow Count	Sample	USCS	Description	Well Const.
	60				
65				Slotted PVC casing → Sand pack →	
70					
75		75	SP	Sand: fine to med., with coarse pebbles dense, tan, lt. brown  Bottom of hole	
				BORING TERMINATED AT 75' DATE OF DRILLING: JULY 12, 1985 DRILLING DONE BY: JEFF FRIEDMAN	

J.H. KLEINFELDER & ASSOCIATES GEOTECHNICAL CONSULTANTS • MATERIALS TESTING		So. Chemical Co. SANTA FE SPRINGS, CALIFORNIA		PLATE  <div style="font-size: 2em; font-weight: bold; text-align: center;">6</div>
PREPARED BY: _____ DATE: _____		<div style="font-size: 1.2em; font-weight: bold;">LOG of BORING MW-8</div>		
CHECKED BY: _____ DATE: _____		PROJECT NO. Q1014-2		



DEPTH (feet)	Blow Count	Sample	USCS	Description	Well Const.
0				6" concrete	
				Locking well cap	
				PVC cap	
5	10	5	ML	Silt, silt with fine sand, black, soft, very moist	
10	30	10		No recovery	
				Cement grout	
				Blank PVC casing	
15	39	15	SP	Sand: fine sand with interbedded silt lens, tan-reddish, med. dense, moist	
20	68	20	SW	Sand: med. to coarse sand with pebbles up to ½", tan, very dense, damp	
25	99/4	25	SW	Sand: coarse sand with ground, grey pebbles up to 1". V. dense, moist	
30					

J.H. KLEINFELDER & ASSOCIATES  
 GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



So. Cal. Chemical Co.  
 SANTA FE SPRINGS, CALIFORNIA  
 LOG of BORING MW-9


PLATE

7

PREPARED BY: DATE:


CHECKED BY: DATE:

PROJECT NO. Q1014-2



J.H. KLEINFELDER & ASSOCIATES GEOTECHNICAL CONSULTANTS * MATERIALS TESTING		So. Cal. Chemical Co. SANTA FE SPRINGS, CALIFORNIA		PLATE  <b>7</b>
PREPARED BY: _____ DATE: _____		<b>LOG of BORING MW-9</b>		
CHECKED BY: _____ DATE: _____		PROJECT NO. Q1014-2		

DEPTH (feet)	Blow Count	Sample	USCS	Description	Well Const.
	60				
65				Sand pack →	
70				Slotted PVC CASING →	
75					
	100/ 2		SM	Silty sand, med. - CRS, brown, V. dense, <u>wet</u>	
				BORING TERMINATED AT 77' DATE OF DRILLING: JULY 10, 1985 DRILLING DONE BY: JEFF FRIEDMAN	

**J.H. KLEINFELDER & ASSOCIATES** 

GEOTECHNICAL CONSULTANTS • MATERIALS TESTING

So. Cal. Chemical Co.

SANTA FE SPRINGS, CALIFORNIA

**LOG of BORING MW-9**

PLATE

**7**

PREPARED BY:	DATE:	
CHECKED BY:	DATE:	
PROJECT NO. Q1014-2		

DEPTH (feet)

DEPTH (feet)	Blow Count	Sample	USCS	Description	Well Const.
30					
				cement grout	
				blank PVC casing	
35	64	35		No recovery	
40					
				Bentonite	
				sand pack	
45	66	45	CL	Clay, lt.brown, reddish stain, very moist	
50			CL	Clay	
55				slotted PVC casing	
60					

J.H. KLEINFELDER & ASSOCIATES  
GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



So. Cal. Chemical

PLATE

LOG of BORING MW-10


8

PREPARED BY: GH DATE: 7-85

CHECKED BY: DATE:

PROJECT NO. Q1014-2

DEPTH (feet)

Blow Count	Sample	USCS	Description	Well Const.
60		SP	Sand, fine	 <p>sand pack</p> <p>slotted PVC casing</p>
65				
70				
75				
80				
85				

Boring terminated at 75'  
Date of drilling was 4-10-85  
Materials logged by K. Durand

J.H. KLEINFELDER & ASSOCIATES  
GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



So. Cal. Chemical

PLATE

8

LOG of BORING MW-10

PREPARED BY: GH DATE: 7-85

CHECKED BY: DATE:

PROJECT NO. Q1014-2

DEPTH (feet)	Blow Count	Sample	USCS	Description	Well Const.
	0			SM	4" concrete Silty sand, black, moist slant at 30
5	9	5	ML	Silt, silt with fine sand, black medium, moist	
10	75	10	ML	Sandy silt, silt with fine sand brown, black-reddish, very stiff very moist	
15	52	15	SP	Sand, med. to fine sand brown, dense, damp	
20	20	99 +	SW	Sand, med to coarse, very little fines, tan, very dense, damp	
25					
30					

J.H. KLEINFELDER & ASSOCIATES
GEOTECHNICAL CONSULTANTS • MATERIALS TESTING

PREPARED BY: GH
DATE: 7-85

CHECKED BY:
DATE:

So. Calif. Chemical

LOG of BORING B1

PROJECT NO. Q1014-2

PLATE

9

DEPTH (feet)

	Blow Count	Sample	USCS	Description	Well Const.
30	80	30	SP	Sand med.to coarse sand tan, very dense, damp , only 3" sample	
35					
40	78		ML	sandy silt, silt with fine sand drk.brn, very stiff, moist	
45					
50	82	50	CL	Clay,very stiff, brown-green, wet	
55				Boring terminated at 50 feet Date of drilling was 7-9-85 Material logged by K. Durand	
60					

J.H. KLEINFELDER & ASSOCIATES  
GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



So. Calif. Chemical

PLATE

9

LOG of BORING B1

PREPARED BY: GH DATE: 7-85

CHECKED BY: DATE:

PROJECT NO. Q1014-2

DEPTH (feet)

Blow Count	Sample	USCS	Description	Well Const.
0			6" concrete	
			Slant at 28°	
		SP	Sand, fine sand black, moist	
5	39	5	ML/ CL	
			Silt/clay brown, very stiff, dry	
10	78	10	CL	
			clay, brown clay very stiff-hard, damp	
15	15	64	SP	
			Sand, med.sand, lt brown-tan very dense dry	
20	20	22	Sp	
			Sand, med. sand tan-red med. dense, dry	
25	25	76		
			no recovery	
30				

J.H. KLEINFELDER & ASSOCIATES  
GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



So. Cal. Chemical

PLATE

LOG of BORING B-2

10

PREPARED BY: GH DATE: 7-85

CHECKED BY: DATE:

PROJECT NO. Q1014-2



DEPTH (feet)

Blow Count	Sample	USCS	Description	Well Const.
30	99/3	30	SP ML sand, med. to coarse sand lt.brown tan very dense dry Sandy silt, lt.brown-tan, very stiff moist	
35	68	10	ML clayey silt, silt with clay, tan-reddish stiff damp	
40	96/4	40	CL silty clay, very silty dark grey, moist	
45	Boring Terminated at 40 feet Date of drilling was 7-9-85 Materials logged by K. Durand			
50				
55				
60				

J.H. KLEINFELDER & ASSOCIATES  
GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



So. Calif. Chemical

PLATE

10


LOG of BORING B-2

PREPARED BY: GH DATE: 7-85

CHECKED BY: DATE:


PROJECT NO. Q1014-2

DEPTH (feet)	Blow Count	Sample	USCS	Description	Well Const.
	0				6" concrete
			SM	Silty sand, fine sand & silt with pebbles up to 3/4", damp	
5	20	5	SM	Silty sand, fine sand and silt, med.dense damp, drk.brown	
10	41	10	SM	Silty sand, fine sand and silt dense, moist drk.brown	
15	52	15	SP	Sand, med. sand, tan,very dense,moist	
20				Boring terminated at 15'. Date of drilling was 7/8/85. Materials logged by K. Durand.	
25					
30					

J.H. KLEINFELDER & ASSOCIATES  GEOTECHNICAL CONSULTANTS • MATERIALS TESTING		So. Calif. Chemical  <b>LOG of BORING</b> B-3 PROJECT NO. Q1014-2	PLATE  <b>11</b>
PREPARED BY: GH      DATE: 7-85			
CHECKED BY:              DATE:			

DEPTH (feet)	Blow Count	Sample	USCS	Description	Well Const.
	0			SP	6" concrete Sand, med. sand with pebbles up to 3/8" brown, dry
5	33	5	ML	Silt with fine sand yellow stain, very stiff, dry	
10	54	10	ML	Silt with fine sand, yellow-brown, very stiff, dry-damp	
15	71+	15	ML	Silt with fine sand, brown, very stiff, damp	
20	100+	20	SP	Sand, med. to coarse sand with 1/2" rounded pebbles drk.brown-reddish very dense, damp	
25	97	25	SP	Sand coarse to med.sand tan-grey, very dense damp	
30					

J.H. KLEINFELDER & ASSOCIATES  
GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



So. Cal. Chemical  
  
LOG of BORING B-4  
  
PROJECT NO. Q1014-2

PLATE  
  
12

PREPARED BY: GH      DATE: 7-85  
CHECKED BY:              DATE:

DEPTH (feet)

30

Blow Count	Sample	USCS	Description	Well Const.
88	30	ML SP	<p>Silt &amp; Sand, brown very dense, damp</p> <p>Boring terminated at 30 feet Date of drilling was 7-9-85 Materials logged by K. Durand</p>	

J.H. KLEINFELDER & ASSOCIATES  
GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



So. Cal. Chemical

PLATE

LOG of BORING B-4

12

PREPARED BY: GH DATE: 7-85

CHECKED BY: DATE:

PROJECT NO. Q1014-2

DEPTH (feet)

	Blow Count	Sample	USCS	Description	Well Const.
0				6" concrete	
5	14	5	ML	Sandy silt: silt with fine sand, dark brown, med. stiff, moist	
10	20	10	ML	Sand silt, silt with fine sand and clay, brown-reddish, stiff, dry	
15	31	15	ML	Silt with clay, brown-reddish, stiff, damp	
20	91/4	20	SP	Med. to fine sand, grey-brown, very dense damp	
25	73	25	SW	gravelly sand, sand with pebbles up to 1 1/2" dia. grey, hard, damp	
30					

J.H. KLEINFELDER & ASSOCIATES  
GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



So. Cal. Chemical

PLATE

LOG of BORING B5

13

PREPARED BY: GH DATE: 7-85

CHECKED BY: DATE:

PROJECT NO. Q1014-2

DEPTH (feet)

30

Blow Count	Sample	USCS	Description	Well Const.
91/5	30	SW	<p>Sand- med. to coarse sand, grey very dense, moist/wet</p> <p>Boring Terminated at 30 feet Date of drilling was 7-12-85 Materials logged by K. Durand</p>	

J.H. KLEINFELDER & ASSOCIATES  
GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



So. Cal. Chemical

LOG of BORING B5

PREPARED BY: GH DATE: 7-85

CHECKED BY: DATE:

PROJECT NO. Q1014-2

PLATE

13

DEPTH (feet)

Blow Count	Sample	USCS	Description	Well Const.
30 57		ML	Sandy silt, silt with coarse sand very stiff moist, wet  Boring terminated at 30 feet Date of drilling was 7-9-85 Materials logged by K. Durand	

J.H. KLEINFELDER & ASSOCIATES  
GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



So. Cal. Chemical

LOG of BORING

B-6

PLATE

14


PREPARED BY: GH DATE: 7-85

CHECKED BY: DATE:


PROJECT NO. Q1014-2

DEPTH (feet)	Blow Count	Sample	USCS	Description	Well Const.
	0				
5	14	5	ML CL	Silt/clay, yellow, soft, moist	
10	40	10		No recovery	
15	41	15	SP	Sand, fine sand with silt, brown reddish, very dense, dry	
20	70	20	SP	Sand, med. to coarse sand red-brown very dense moist, very little fine	
25	93 +	25	GP SW	Sandy gravel, gravelly sand, rounded pebbles up to 1/2", very dense, damp	
30					

J.H. KLEINFELDER & ASSOCIATES GEOTECHNICAL CONSULTANTS * MATERIALS TESTING 	So. Cal. Chemical	PLATE  <b>14</b>
	LOG of BORING B-6 PROJECT NO. Q1014-2	
PREPARED BY: GH DATE: 7-85 CHECKED BY: DATE:		





J.H. KLEINFELDER & ASSOCIATES  
GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



**SOUTHERN CALIFORNIA  
CHEMICAL COMPANY**

PLATE

**15**

**REGIONAL CROSS SECTION**

PREPARED BY: DATE:



CHECKED BY: DATE:

PROJECT NO.

# EXPLANATION

 MW-11 MONITORING WELL  
 ELEVATION (FEET ABOVE MEAN SEA LEVEL)  
 OF GROUND WATER ON 9/20/85

 106.00  
 GROUNDWATER CONTOUR  
 LINE OF EQUAL ELEVATION ON 9/20/85



J.H. KLEINFELDER & ASSOCIATES  
 GEOTECHNICAL CONSULTANTS • MATERIALS TESTING  
 PROJECT NO. Q 1014-2

SOUTHERN CALIFORNIA CHEMICAL  
 SANTA FE SPRINGS, CA.  
 GROUNDWATER ELEVATION  
 CONTOUR MAP  
 SEPTEMBER 20, 1985


PLATE  
 16

Quantity	SCC Materials (Prior to Pretreatment as Required by EPA & LACSD)	pH 13-14 Solution in Tank Prior to Treatment	Neutralization*	Metals Precipitation (By Addition of Reducing Agent such as Sodium Sulfide)	Solution After Precipitation	Oxidation if Needed	Effluent Discharged to LACSD 22,000-27,000 gpd pH above 6
14.0- 2 (Inad- 3 vertent)	Cupric oxide	$CuO \rightarrow$	$\rightarrow$	$CuO \downarrow$			
15.	Cupric sulfate solution	$CuSO_4 \rightarrow$	$\rightarrow$	$+ Na_2S \rightarrow CuS \downarrow$	$+ (NH_4)_2SO_4$ &/or $Na_2SO_4$	$\rightarrow$	
16.	Cupric chloride solution	$CuCl_2 \rightarrow$	$\rightarrow$	$+ Na_2S \rightarrow CuS \downarrow$	$+ NH_4Cl$ &/or $NaCl$	$\rightarrow$	
17.	Copper pyrophosphate solution	$Cu_2P_2O_7 \rightarrow$	$\rightarrow$	$+ Na_2S \rightarrow 2CuS \downarrow$	$+ (NH_4)_2HPO_4$ &/or $Na_2HPO_4$	$\rightarrow$	
18.	Cupric nitrate solution	$Cu(NO_3)_2 \rightarrow$	$\rightarrow$	$+ Na_2S \rightarrow CuS \downarrow$	$+ NaNO_3$ &/or $NH_4NO_3$	$\rightarrow$	
19.	Copper hydroxide solution	$Cu(OH)_2 \rightarrow$	$\rightarrow$	$Cu(OH)_2 \downarrow$			
20.	Cuprous chloride solution	$CuCl \rightarrow$	$\rightarrow$	$+ Na_2S \rightarrow CuS \downarrow$	$+ NH_4Cl$ &/or $NaCl$	$\rightarrow$	
21.0-100 gpd	(Materials resulting from roadway washdown; routine plant cleanup (incl. dirt); truck washing; container & tank cleaning; drum triple rinsing; cleanup of spills; rinse waters)	Dirt $\rightarrow$ (w/ or w/o M)	$\rightarrow$	Dirt $\downarrow$ $CuS \downarrow$ $NiS \downarrow$ $PbS \downarrow$ $SnS \downarrow$	$+ H_2O$	$\rightarrow$	
A: 50-100 gpd, or as needed	Hydrogen peroxide				If any free sulfides	$+ H_2O_2 \rightarrow$	Sulfates
B: As needed	Chlorine (to kill free sulfides as needed)	$Cl_2$			If any free sulfides	$+ Cl_2 \rightarrow$	$NaOCl$
C: 0-50 gpd	Perchloric acid				If any free sulfides	$+ HClO_4 \rightarrow$	$NaCl + O_2 \uparrow$
				Buildup Precipitates in Bottom of Tanks			
	*20% chromic-sulfuric acid soln in water, pH 0-1 (mixed with hi pH precipitate once every 30-60 days; otherwise, stored in separate above-ground tank).		$\rightarrow$	3.5% $CuS$ ; 3% $NaCl$ ; 2.5% $Cr^{+3}$ S; 3% metal hydroxide; 2% metal sulfide; 2.7% $FeS$ ; 0.3% $ZnS$ ; 0.5% other; 1% $(NH_4)_2SO_4$ ; 81% water.			
						$\rightarrow$ Hauled away to appropriate site or sold.	
	*May add any of the neutralizing acids listed in this column, alone or in combinations; may contain metals.						
	*Prior to 1983, this material did not enter wastewater system at all. It was taken directly from tank straight to Class I site.						


1 = Metals, such as Fe, Cu, Zn, Ni, Ti, Cu, Cr, As, etc.

Reactions, quantities, frequencies of  
Chemicals in SCC's Wastewater Neutralization System


Quantity	SCC Materials (Prior to Pretreatment as Required by EPA & LACSD)	pH 13-14 Solution in Tank Prior to Treatment	Neutralization*	Metals Precipitation (By Addition of Reducing Agent such as Sodium Sulfide)	Solution After Precipitation	Oxidation if Needed	Effluent Discharged to LACSD 22,000-27,000 gpd pH above 6
1.0-1000 gpd	(Ferric chloride solution, $\text{FeCl}_3$ (may contain metals such as Ni, Zn, Cr, Pb, Sn, As, etc., e.g.))	~8% $\text{FeOH}$ + $\text{NaCl}$ (as result of exposure to hi pH media)	→	+ $\text{Na}_2\text{S}$ → $\text{FeOH}\downarrow$ , $\text{PbS}\downarrow$ , $\text{NiS}\downarrow$ , $\text{SnS}\downarrow$ , $\text{Cr}\equiv\text{S}\downarrow$ , $\text{ZnS}\downarrow$ , $\text{AsS}\downarrow$ + $\text{NaCl}$			
2.0-2000 gpd	(Ferrous chloride solution, $\text{FeCl}_2$ (same as above))						
3.15-2000 gpd	10% sodium chloride solution	$\text{NaCl}$	→				
4.0-2000 gpd	1-2% sodium hydroxide solution	$\text{NaOH}$	→	+ $\text{H}_2\text{SO}_4$ (w/ or w/o M)	+ $\text{Na}_2\text{S}$ → $\text{PbS}\downarrow$ , $\text{AsS}\downarrow$ , $\text{FeS}\downarrow$	+ $(\text{NH}_4)_2\text{SO}_4$ &/or $\text{Na}_2\text{SO}_4$	
5.0-2000 gpd	Residual sodium carbonate	$\text{NaCO}_3$	→	+ $\text{HCl}$ (w/ or w/o M)	+ $\text{Na}_2\text{S}$ → $\text{TiS}\downarrow$ , $\text{FeS}\downarrow$ , $\text{SnS}\downarrow$	+ $\text{NH}_4\text{Cl}$ &/or $\text{NaCl}$	
6.0-2000 gpd	Ammonium hydroxide	$\text{NH}_4\text{OH}$	→	+ $\text{H}_3\text{PO}_4$ (w/ or w/o M)	+ $\text{Na}_2\text{S}$ → $\text{MS}\downarrow$	+ $(\text{NH}_4)_2\text{HPO}_4$ &/or $\text{Na}_2\text{HPO}_4$	
7.0-2000 gpd	<1% free ammonium chloride soln	$\text{NH}_4\text{Cl}$	→	+ $\text{HNO}_3$ (w/ or w/o M)	+ $\text{Na}_2\text{S}$ → $\text{MS}\downarrow$	+ $\text{NH}_4\text{NO}_3$ &/or $\text{NaNO}_3$	
8.0-2000 gpd	<1% free ammonia + other water	$\text{NH}_3 + \text{H}_2\text{O}$	→	Citric acid (w/ or w/o M)	+ $\text{Na}_2\text{S}$ → $\text{MS}\downarrow$	+ Ammonium citrate &/or sodium citrate	
9.0-2000 gpd	Cupric ammonium chloride solution	$\text{Cu} \cdot 2(\text{NH}_3) \cdot 2(\text{NH}_4)\text{Cl}_2$	→	+ $\text{Na}_2\text{S}$ → $\text{CuS}\downarrow$	+ $2\text{NH}_4\text{OH} + 2\text{NH}_4\text{Cl}$		
10.0-2000 gpd	1-2% ammonium sulfate solution**	$(\text{NH}_4)_2\text{SO}_4$	→				
11.0-200 gpd	Ammonium bifluoride soln, $\text{NH}_4\text{HF}_2$ pH 3; w/Sn, Pb, Cu, etc.	$\text{NH}_4\text{F}$ (as result of exposure to hi pH media)	→	+ $\text{Na}_2\text{S}$ → $\text{SnS}\downarrow$ , $\text{PbS}\downarrow$ , $\text{CuS}\downarrow$	+ $\text{NH}_4\text{F}$		$2\text{NH}_4\text{F}$
12.0-100 gpd	Nickel sulfate solution	$\text{NiSO}_4$	→	+ $\text{Na}_2\text{S}$ → $\text{NiS}\downarrow$	+ $(\text{NH}_4)_2\text{SO}_4$ &/or $\text{Na}_2\text{SO}_4$		
13.0-100 gpd	Zinc sulfate solution	$\text{ZnSO}_4$	→	+ $\text{Na}_2\text{S}$ → $\text{ZnS}\downarrow$	+ $(\text{NH}_4)_2\text{SO}_4$ &/or $\text{Na}_2\text{SO}_4$		
*May add any of the neutralizing acids listed in this column, alone or in combinations; may contain metals. **Normally sold rather than discharged.							




VIEW NORTH



VIEW EAST




VIEW NORTH




VIEW WEST

SCALE: 1"=16'


10,000 SAMPLE ANALYZED AT LABORATORY OF BROWN & CALDWELL  
 (23,000) SAMPLE ANALYZED AT LABORATORY OF SOUTHERN CALIFORNIA CHEMICAL




VIEW NORTH



VIEW EAST



VIEW NORTH



VIEW WEST

SCALE: 1" = 16'

- 4.5 SAMPLE ANALYZED AT LABORATORY OF BROWN & CALDWELL
- (4.2) SAMPLE ANALYZED AT LABORATORY OF SOUTHERN CALIFORNIA CHEMICAL

J.H. KLEINFELDER & ASSOCIATES  
GEOTECHNICAL CONSULTANTS • MATERIALS TESTING


SOUTHERN CALIFORNIA CHEMICAL  
SANTA FE SPRINGS, CA.

CROSS SECTIONS  
WITH CONCENTRATIONS OF  
OF PH IN SOIL


PROJECT NO. Q1014-2

PLATE


19




VIEW NORTH



VIEW EAST



VIEW NORTH



VIEW WEST

SCALE: 1" = 16'


450 SAMPLE ANALYZED AT LABORATORY OF BROWN & CALDWELL  
 (17) SAMPLE ANALYZED AT LABORATORY OF SOUTHERN CALIFORNIA CHEMICAL

J.H. KLEINFELDER & ASSOCIATES  
 GEOTECHNICAL CONSULTANTS • MATERIALS TESTING


SOUTHERN CALIFORNIA CHEMICAL  
 SANTA FE SPRINGS, CA.  
 CROSS SECTIONS  
 WITH CONCENTRATIONS OF  
 COPPER IN SOIL (MG/KG)

PROJECT NO. Q1014-2


PLATE  
 20




VIEW NORTH



VIEW EAST



VIEW NORTH



VIEW WEST

SCALE: 1" = 16'

J.H. KLEINFELDER & ASSOCIATES  
GEOTECHNICAL CONSULTANTS • MATERIALS TESTING



SOUTHERN CALIFORNIA CHEMICAL  
SANTA FE SPRINGS, CA.

CROSS SECTIONS  
WITH CONCENTRATIONS OF  
CHLORIDE IN SOIL (MG/KG)

PLATE


21

PROJECT NO. Q1014-2







SCALE: 1" = 16'




VIEW NORTH



VIEW EAST



VIEW NORTH



VIEW WEST

SCALE: 1" = 16'

J. H. KLEINFELDER & ASSOCIATES

APPENDIX A



LOG NO: P85-07-363

Received: 24 JUL 85

Reported: 19 AUG 85

Ken Durand  
J.H. Kleinfelder & Assoc.  
901 W. Victoria St., Suite G  
Compton, CA 90220

Project: Q-1014-2

## REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, AQUEOUS SAMPLES					DATE SAMPLED
07-363-1	W-00-137/W-00-138 Q-1014-2					24 JUL 85
07-363-2	W-02-140 Q-1014-2					24 JUL 85
07-363-3	W-05-144/W-05-145 Q-1014-2					24 JUL 85
07-363-4	W-04-146/W-04-147 Q-1014-2					24 JUL 85
07-363-5	W-00-149/W-00-150 Q-1014-2					24 JUL 85
07-363-6	W-03-152/W-03-153 Q-1014-2					24 JUL 85
PARAMETER	07-363-1	07-363-2	07-363-3	07-363-4	07-363-5	07-363-6
Purgeable Priority Pollutants						
Extraction	08/07/85	08/07/85	08/07/85	08/07/85	08/07/85	08/07/85
1,1-Dichloroethane, ug/L	<1	4	<1	100	<1	6
1,1-Dichloroethylene, ug/L	<1	3	<1	100	<1	14
Acrolein, ug/L	<10	<10	<10	<500	<10	<10
Acrylonitrile, ug/L	<10	<10	<10	<500	<10	<10
Benzene, ug/L	16	<1	5	<50	14	9
Carbon Tetrachloride, ug/L	<1	<1	3	<50	<1	73
Chloroform, ug/L	<1	<1	2	<50	<1	46
Ethylbenzene, ug/L	<1	<1	<1	3000	<1	<1
Methylene Chloride, ug/L	<1	<1	<1	100	16	<1
Trichloroethylene, ug/L	<1	21	10	550	<1	320
Toluene, ug/L	14	<1	1	8300	13	2
trans-1,2-Dichloroethylene, ug/L	<1	9	<1	<50	<1	1
Other Purgeable Priority Pollutants,	<1	<1	<1	<50	<1	<1

LOG NO: P85-07-363

Received: 24 JUL 85

Reported: 19 AUG 85

Ken Durand  
J.H. Kleinfelder & Assoc.  
901 W. Victoria St., Suite G  
Compton, CA 90220

Project: Q-1014-2

# REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, AQUEOUS SAMPLES	DATE SAMPLED
07-363-1	W-00-137/W-00-138 Q-1014-2	24 JUL 85
07-363-2	W-02-140 Q-1014-2	24 JUL 85
07-363-3	W-05-144/W-05-145 Q-1014-2	24 JUL 85
07-363-4	W-04-146/W-04-147 Q-1014-2	24 JUL 85
07-363-5	W-00-149/W-00-150 Q-1014-2	24 JUL 85
07-363-6	W-03-152/W-03-153 Q-1014-2	24 JUL 85
PARAMETER	07-363-1 07-363-2 07-363-3 07-363-4 07-363-5 07-363-6	

Semi-Quantified Results \*\*  
Xylene Isomers, ug/L

--- --- --- 10,000 --- ---

\*\* Quantification based upon comparison of total ion count of the compound with that of the nearest internal standard.

A-2

LOG NO: P85-07-363

Received: 24 JUL 85

Reported: 19 AUG 85

Ken Durand  
J.H. Kleinfelder & Assoc.  
901 W. Victoria St., Suite G  
Compton, CA 90220

Project: Q-1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, AQUEOUS SAMPLES	DATE SAMPLED
07-363-7	W-02-142 Q-1014-2	24 JUL 85
PARAMETER	07-363-7	
Chromium, mg/L	<0.033	
Dissolved Digestion, Date	07/25/85	
hexavalent Chromium, mg/L	<0.033	

A-3

LOG NO: P85-07-363

Received: 24 JUL 85

Reported: 19 AUG 85

Ken Durand  
J.H. Kleinfelder & Assoc.  
901 W. Victoria St., Suite G  
Compton, CA 90220

Project: Q-1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, AQUEOUS SAMPLES	DATE SAMPLED
07-363-8	W-04-148 Q-1014-2	24 JUL 85
PARAMETER	07-363-8	
Chromium, mg/L	550	
Cadmium, mg/L	0.92	
Dissolved Digestion, Date	07/25/85	
hexavalent Chromium, mg/L	500	
Nitrate Nitrogen		
Nitrate (as NO3), mg/L	55	
Nitrate (as N), mg/L	12	

A-4

LOG NO: P85-07-363

Received: 24 JUL 85

Reported: 19 AUG 85

Ken Durand  
J.H. Kleinfelder & Assoc.  
901 W. Victoria St., Suite G  
Compton, CA 90220

Project: Q-1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, AQUEOUS SAMPLES	DATE SAMPLED
7-363-9	W-03-154 Q-1014-2	24 JUL 85
PARAMETER	07-363-9	
Cadmium, mg/L	<0.011	
Chromium, mg/L	<0.033	
Dissolved Digestion, Date	07/25/85	
Hexavalent Chromium, mg/L	<0.033	

Edward Wilson, Laboratory Director

A-5



BROWN AND CALDWELL



ANALYTICAL LABORATORIES

RECEIVED

SEP 06 1985

JHK & A LA

LOG NO: P85-08-042

Received: 02 AUG 85

Reported: 03 SEP 85

Ken Durand  
J. H. Kleinfelder & Associates  
901 W. Victoria Street, Suite G  
Compton, California 90220

Project: Q-1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, AQUEOUS SAMPLES	DATE SAMPLED
08-042-1	W-00-155thrul58 Q-1014-2	02 AUG 85
PARAMETER	08-042-1	
Q aduplicate TOC:		
TOC, Average, mg/L	<3.0	
TOC, Standard Deviation, mg/L	0.0	
TOC, 1st Replicate, mg/L	<3.0	
TOC, 2nd Replicate, mg/L	<3.0	
TOC, 3rd Replicate, mg/L	<3.0	
TOC, 4th Replicate, mg/L	<3.0	

A-6

LOG NO: P85-08-042

Received: 02 AUG 85

Reported: 03 SEP 85

Ken Durand  
J. H. Kleinfelder & Associates  
901 W. Victoria Street, Suite G  
Compton, California 90220

Project: Q-1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, AQUEOUS SAMPLES	DATE SAMPLED		
08-042-2	W-07-159thru173 Q-1014-2	02 AUG 85		
08-042-3	W-09-189thru203 Q-1014-2	02 AUG 85		
08-042-4	W-11-174thru188 Q-1014-2	02 AUG 85		
PARAMETER	08-042-2	08-042-3	08-042-4	
Cadmium, mg/L	<0.01	<0.01	<0.01	
Chromium, mg/L	<0.03	<0.03	<0.03	
Dissolved Digestion, Date	08/06/85	08/06/85	08/06/85	
Chloride, mg/L	380	300	220	
Hexavalent Chromium, mg/L	<0.5	<0.5	<0.5	
Nitrate Nitrogen				
Nitrate (as NO <sub>3</sub> ), mg/L	120	6.3	5.2	
Nitrate (as N), mg/L	27	1.4	1.2	
Quadruplicate Conductivity:				
Sp. Cond., Average, umhos/cm	2700	2200	1600	
Sp. Cond., Std. Deviation, umhos/cm	43	0	43	
Sp. Cond., 1st Replicate, umhos/cm	2700	2200	1600	
Sp. Cond., 2nd Replicate, umhos/cm	2700	2200	1700	
Sp. Cond., 3rd Replicate, umhos/cm	2800	2200	1600	
Sp. Cond., 4th Replicate, umhos/cm	2700	2200	1600	

A-7

LOG NO: P85-08-042

Received: 02 AUG 85

Reported: 03 SEP 85

Ken Durand  
J. H. Kleinfelder & Associates  
901 W. Victoria Street, Suite G  
Compton, California 90220

Project: Q-1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, AQUEOUS SAMPLES	DATE SAMPLED		
08-042-2	W-07-159thru173 Q-1014-2	02 AUG 85		
08-042-3	W-09-189thru203 Q-1014-2	02 AUG 85		
08-042-4	W-11-174thru188 Q-1014-2	02 AUG 85		
PARAMETER		08-042-2	08-042-3	08-042-4
Quadruplicate pH:				
pH, Average, Units		6.3	6.4	6.6
pH, Standard Deviation, Units		0.04	0.0	0.04
pH, 1st Replicate, Units		6.4	6.4	6.6
pH, 2nd Replicate, Units		6.3	6.4	6.7
pH, 3rd Replicate, Units		6.3	6.4	6.6
pH, 4th Replicate, Units		6.3	6.4	6.6
Quadruplicate TOC:				
TOC, Average, mg/L		260	210	54
TOC, Standard Deviation, mg/L		21	0.0	1.7
TOC, 1st Replicate, mg/L		270	210	56
TOC, 2nd Replicate, mg/L		280	210	52
TOC, 3rd Replicate, mg/L		240	210	53
TOC, 4th Replicate, mg/L		240	210	54

A-8



LOG NO: P85-08-042

Received: 02 AUG 85


Reported: 03 SEP 85

Ken Durand  
J. H. Kleinfelder & Associates  
901 W. Victoria Street, Suite G  
Compton, California 90220

Project: Q-1014-2

### REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, AQUEOUS SAMPLES	DATE SAMPLED		
08-042-2	W-07-159thru173 Q-1014-2	02 AUG 85		
08-042-3	W-09-189thru203 Q-1014-2	02 AUG 85		
0 -042-4	W-11-174thru188 Q-1014-2	02 AUG 85		
PARAMETER		08-042-2	08-042-3	08-042-4
Quadruplicate TOX:				
TOX, 1st Replicate, mg/L		0.069	0.11	<0.05
TOX, 2nd Replicate, mg/L		0.10	0.12	<0.05
TOX, 3rd Replicate, mg/L		0.091	0.13	<0.05
TOX, 4th Replicate, mg/L		0.063	0.15	0.098
TOX, Average, mg/L		0.081	0.13	0.062
TOX, Standard Deviation, mg/L		0.018	0.017	0.024

  
Edward Wilson, Laboratory Director

A-10

BROWN AND CALDWELL



ANALYTICAL LABORATORIES

RECEIVED

SEP 05 1985

JHK &amp; A LA

LOG NO: P85-08-064

Received: 05 AUG 85

Reported: 03 SEP 85

Ken Durand  
J. H. Kleinfelder & Associates  
901 W. Victoria Street, Suite G  
Compton, California 90220

Project: Q1014-2

## REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, AQUEOUS SAMPLES	DATE SAMPLED			
08-064-1	W-00-204thru218 Q1014-2	05 AUG 85			
08-064-2	W-00-264thru278 Q1014-2	05 AUG 85			
0 -064-3	W-4A-249thru263 Q1014-2	05 AUG 85			
08-064-4	W-08-234thru248 Q1014-2	05 AUG 85			
PARAMETER		08-064-1	08-064-2	08-064-3	08-064-4
Cadmium, mg/L		<0.01	<0.01	<0.01	<0.01
Chromium, mg/L		<0.03	<0.03	<0.03	<0.03
Dissolved Digestion, Date		08/06/85	08/06/85	08/06/85	08/06/85
Hexavalent Chromium, mg/L		<0.5	<0.5	<0.5	<0.5
Nitrate Nitrogen					
Nitrate (as NO3), mg/L		9.3	0.10	20	5.8
Nitrate (as N), mg/L		2.1	0.44	4.5	1.3
Quadruplicate pH:					
1, Average, Units		5.6	4.2	6.8	6.6
1, Standard Deviation, Units		0.0	0.0	0.05	0.04
pH, 1st Replicate, Units		5.6	4.2	6.8	6.6
pH, 2nd Replicate, Units		5.6	4.2	6.8	6.6
pH, 3rd Replicate, Units		5.6	4.2	6.7	6.7
pH, 4th Replicate, Units		5.6	4.2	6.8	6.6

A-11

LOG NO: P85-08-064

Received: 05 AUG 85

Reported: 03 SEP 85

Ken Durand  
J. H. Kleinfelder & Associates  
901 W. Victoria Street, Suite G  
Compton, California 90220

Project: Q1014-2

# REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, AQUEOUS SAMPLES	DATE SAMPLED			
08-064-1	W-00-204thru218 Q1014-2	05 AUG 85			
08-064-2	W-00-264thru278 Q1014-2	05 AUG 85			
08-064-3	W-4A-249thru263 Q1014-2	05 AUG 85			
08-064-4	W-08-234thru248 Q1014-2	05 AUG 85			
PARAMETER		08-064-1	08-064-2	08-064-3	08-064-4
Quadruplicate Conductivity:					
Sp. Cond., Average, umhos/cm		52	190	1500	2800
p. Cond., Std. Deviation, umhos/cm		0	5	47	43
Sp. Cond., 1st Replicate, umhos/cm		52	190	1500	2800
Sp. Cond., 2nd Replicate, umhos/cm		52	180	1500	2800
p. Cond., 3rd Replicate, umhos/cm		52	180	1400	2800
p. Cond., 4th Replicate, umhos/cm		52	190	1500	2700
Quadruplicate TOC:					
OC, Average, mg/L		<3	<3	40	99
OC, Standard Deviation, mg/L		0	0	3.8	3.5
TOC, 1st Replicate, mg/L		<3	<3	38	99
TOC, 2nd Replicate, mg/L		<3	<3	37	96
TOC, 3rd Replicate, mg/L		<3	<3	46	103
TOC, 4th Replicate, mg/L		<3	<3	40	99

A-12

LOG NO: P85-08-064

Received: 05 AUG 85

Reported: 03 SEP 85

Ken Durand  
J. H. Kleinfelder & Associates  
901 W. Victoria Street, Suite G  
Compton, California 90220

Project: Q1014-2

### REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, AQUEOUS SAMPLES	DATE SAMPLED			
08-064-1	W-00-204thru218 Q1014-2	05 AUG 85			
08-064-2	W-00-264thru278 Q1014-2	05 AUG 85			
8-064-3	W-4A-249thru263 Q1014-2	05 AUG 85			
8-064-4	W-08-234thru248 Q1014-2	05 AUG 85			
PARAMETER		08-064-1	08-064-2	08-064-3	08-064-4
Quadruplicate TOX:					
TOX, 1st Replicate, mg/L		<0.05	<0.05	<0.05	0.53
TOX, 2nd Replicate, mg/L		<0.05	0.052	<0.05	0.16
TOX, 3rd Replicate, mg/L		<0.05	<0.05	<0.05	0.27
TOX, 4th Replicate, mg/L		<0.05	<0.05	<0.05	0.79
TOX, Average, mg/L		<0.05	0.051	<0.05	0.44
TOX, Standard Deviation, mg/L		0.0	0.001	0.0	0.28

A-13



LOG NO: P85-08-064

Received: 05 AUG 85

Reported: 03 SEP 85

Ken Durand  
J. H. Kleinfelder & Associates  
901 W. Victoria Street, Suite G  
Compton, California 90220

Project: Q1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, AQUEOUS SAMPLES	DATE SAMPLED
08-064-5	W-10-219thru233 Q1014-2	05 AUG 85
PARAMETER	08-064-5	
Cadmium, mg/L	<0.01	
Chromium, mg/L	<0.03	
Dissolved Digestion, Date	08/06/85	
Hexavalent Chromium, mg/L	<0.5	
Nitrate Nitrogen		
Nitrate (as NO3), mg/L	<0.44	
Nitrate (as N), mg/L	<0.10	
Quadruplicate pH:		
pH, Average, Units	6.8	
pH, Standard Deviation, Units	0.04	
pH, 1st Replicate, Units	6.8	
pH, 2nd Replicate, Units	6.8	
pH, 3rd Replicate, Units	6.7	
pH, 4th Replicate, Units	6.8	
Quadruplicate Conductivity:		
Sp. Cond., Average, umhos/cm	2100	
Sp. Cond., Std. Deviation, umhos/cm	0	
Sp. Cond., 1st Replicate, umhos/cm	2100	
Sp. Cond., 2nd Replicate, umhos/cm	2100	
Sp. Cond., 3rd Replicate, umhos/cm	2100	
Sp. Cond., 4th Replicate, umhos/cm	2100	

A-14

LOG NO: P85-08-064

Received: 05 AUG 85

Reported: 03 SEP 85

Ken Durand  
J. H. Kleinfelder & Associates  
901 W. Victoria Street, Suite G  
Compton, California 90220

Project: Q1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, AQUEOUS SAMPLES	DATE SAMPLED
08-064-5	W-10-219thru233 Q1014-2	05 AUG 85
PARAMETER	08-064-5	
Quadruplicate TOC:		
TOC, Average, mg/L	440	
TOC, Standard Deviation, mg/L	6.6	
TOC, 1st Replicate, mg/L	430	
TOC, 2nd Replicate, mg/L	440	
TOC, 3rd Replicate, mg/L	440	
TOC, 4th Replicate, mg/L	450	
Quadruplicate TOX:		
TOX, 1st Replicate, mg/L	0.53	
TOX, 2nd Replicate, mg/L	0.11	
TOX, 3rd Replicate, mg/L	0.48	
TOX, 4th Replicate, mg/L	<0.05	
TOX, Average, mg/L	0.17	
TOX, Standard Deviation, mg/L	0.21	

LOG NO: P85-08-064

Received: 05 AUG 85

Reported: 03 SEP 85


Ken Durand  
J. H. Kleinfelder & Associates  
901 W. Victoria Street, Suite G  
Compton, California 90220

Project: Q1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, AQUEOUS SAMPLES	DATE SAMPLED
08-064-5	W-10-219thru233 Q1014-2	05 AUG 85
PARAMETER		08-064-5
Purgeable Priority Pollutants		
Extraction		08/20/85
Acrolein, ug/L		<500
Acrylonitrile, ug/L		<500
Chlorobenzene, ug/L		50
Thylbenzene, ug/L		6500
Methylene Chloride, ug/L		100
Trichloroethylene, ug/L		250
oluene, ug/L		17,000
Other Purgeable Priority Pollutants,		<50
Semi-Quantified Results **		
Xylene Isomers, ug/L		20,000

\*\* Quantification based upon comparison of total ion count of the compound with that of the nearest internal standard.

  
Edward Wilson, Laboratory Director

A-16

J. H. KLEINFELDER & ASSOCIATES

APPENDIX B

RECEIVED

JUL 29 1985

BROWN AND CALDWELL



ANALYTICAL LABORATORIES

JHK &amp; A LA

LOG NO: P85-07-211

Received: 12 JUL 85

Reported: 23 JUL 85

Ken Durand  
 J.H. Kleinfelder & Assoc.  
 901 W. Victoria St., Suite G  
 Compton, CA 90220

Project: Q1014-2

## REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES					DATE SAMPLED
7-211-1	B5-10 Q-1014-2					12 JUL 85
07-211-2	B5-25 Q-1014-2					12 JUL 85
07-211-3	B6-15 Q-1014-2					12 JUL 85
7-211-4	B6-25 Q-1014-2					12 JUL 85
07-211-5	S-4A-10 Q-1014-2					12 JUL 85
07-211-6	S-4A-25 Q-1014-2					12 JUL 85
PARAMETER	07-211-1	07-211-2	07-211-3	07-211-4	07-211-5	07-211-6
Copper, mg/kg	78	160	4100	1400	410	24
Chromium, mg/kg	30	49	5100	1500	14	67
Nickel, mg/kg	26	12	240	98	31	9.7
Zinc, mg/kg	79	34	430	43	110	150
Nitric Acid Digestion, Date	07/15/85	07/15/85	07/15/85	07/15/85	07/15/85	07/15/85

B-1

LOG NO: P85-07-211

Received: 12 JUL 85

Reported: 23 JUL 85


Ken Durand  
J.H. Kleinfelder & Assoc.  
901 W. Victoria St., Suite G  
Compton, CA 90220

Project: Q1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES	DATE SAMPLED
7-211-7	S-08-10 Q-1014-2	12 JUL 85
7-211-8	S-08-25 Q-1014-2	12 JUL 85
07-211-9	S-09-15 Q-1014-2	12 JUL 85
7-211-10	S-09-25 Q-1014-2	12 JUL 85
7-211-11	S-10-10 Q-1014-2	12 JUL 85
07-211-12	S-10-25 Q-1014-2	12 JUL 85

PARAMETER	07-211-7	07-211-8	07-211-9	07-211-10	07-211-11	07-211-12
Copper, mg/kg	61	94	28	18	89	25
Chromium, mg/kg	41	3.7	15	4.3	31	5.3
Nickel, mg/kg	27	<3.1	19	4.6	28	6.4
Zinc, mg/kg	96	54	55	29	100	30
Nitric Acid Digestion, Date	07/15/85	07/15/85	07/15/85	07/15/85	07/15/85	07/15/85

  
Edward Wilson, Laboratory Director

B-2

BROWN AND CALDWELL



ANALYTICAL LABORATORIES

LOG NO: P85-10-038

Received: 02 OCT 85

Reported: 11 OCT 85

Ken Durand  
J. H. Kleinfelder & Associates  
901 W. Victoria Street, Suite G  
Compton, California 90220

Project: Q1014-2

## REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION. SOIL SAMPLES					DATE SAMPLED
1 -038-1	B-3-05 Q1014-2					
10-038-2	B-1-10 Q1014-2					
10-038-3	B-1-15 Q1014-2					
1 -038-4	B-2-15 Q1014-2					
10-038-5	B-2-20 Q1014-2					
10-038-6	B-4-05 Q1014-2					
PARAMETER	10-038-1	10-038-2	10-038-3	10-038-4	10-038-5	10-038-6
Chromium, mg/kg	420	53	13	54	440	10.000
Copper, mg/kg	1200	470	130	390	230	480
Nitric Acid Digestion, Date	10/08/85	10/08/85	10/08/85	10/08/85	10/08/85	10/08/85
pH, Units	8.1	8.0	7.0	3.9	3.9	4.6

B-3

LOG NO: P85-10-038

Received: 02 OCT 85

Reported: 11 OCT 85

Ken Durand  
J. H. Kleinfelder & Associates  
901 W. Victoria Street, Suite G  
Compton, California 90220

Project: Q1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION. SOIL SAMPLES	DATE SAMPLED
10-038-7	B-5-05 Q1014-2	
10-038-8	B-6-05 Q1014-2	
PARAMETER	10-038-7	10-038-8
Chromium, mg/kg	85	3700
Copper, mg/kg	230	460
Nitric Acid Digestion, Date	10/08/85	10/08/85
pH, Units	8.7	4.5

B-41



LOG NO: P85-10-038

Received: 02 OCT 85

Reported: 11 OCT 85

Ken Durand  
J. H. Kleinfelder & Associates  
901 W. Victoria Street, Suite G  
Compton, California 90220

Project: Q1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES	DATE SAMPLED
10-038-9	B-3-15 Q1014-2	
PARAMETER	10-038-9	
Chromium, mg/kg	11	
Nitric Acid Digestion, Date	10/08/85	
Carbonate, mg/kg	0.0	
Chloride, mg/kg	1100	
Sulfate, mg/kg	110	
Ammonia Nitrogen (as N), mg/kg	23	

B-5

LOG NO: P85-10-038

Received: 02 OCT 85

Reported: 11 OCT 85

Ken Durand  
J. H. Kleinfelder & Associates  
901 W. Victoria Street, Suite G  
Compton, California 90220

Project: Q1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION. SOIL SAMPLES	DATE SAMPLED
0-038-10	E-5-15 Q1014-2	
PARAMETER	10-038-10	
Chromium, mg/kg	3200	
Copper, mg/kg	12,000	
Nitric Acid Digestion, Date	10/08/85	
H, Units	4.8	
Carbonate, mg/kg	0.0	
Chloride, mg/kg	1600	
Ammonia Nitrogen (as N), mg/kg	21	
Sulfate, mg/kg	170	

E-6

LOG NO: P85-10-038

Received: 02 OCT 85

Reported: 11 OCT 85

Ken Durand  
J. H. Kleinfelder & Associates  
901 W. Victoria Street, Suite G  
Compton, California 90220

Project: Q1014-2

# REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES	DATE SAMPLED					
0-038-11	B-1-40 Q1014-2						
0-038-12	B-1-50 Q1014-2						
10-038-13	B-2-35 Q1014-2						
0-038-14	B-2-40 Q1014-2						
0-038-15	S-4A-25 Q1014-2						
10-038-16	B-4-25 Q1014-2						
PARAMETER	10-038-11	10-038-12	10-038-13	10-038-14	10-038-15	10-038-16	
Carbonate, mg/kg	0.0	0.0	0.0	0.0	0.0	0.0	
chloride, mg/kg	5100	2600	5500	2900	2700	1400	
Ammonia Nitrogen (as N), mg/kg	29	10	42	11	29	25	
Sulfate, mg/kg	20	71	41	45	79	450	

LOG NO: P85-10-038

Received: 02 OCT 85


Reported: 11 OCT 85

Ken Durand  
J. H. Kleinfelder & Associates  
901 W. Victoria Street, Suite G  
Compton, California 90220

Project: Q1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION. SOIL SAMPLES	DATE SAMPLED			
0-038-17	S-10-25 Q1014-2				
10-038-18	S-09-15 Q1014-2				
10-038-19	S-08-10 Q1014-2				
0-038-20	B-06-15 Q1014-2				
PARAMETER		10-038-17	10-038-18	10-038-19	10-038-20
Carbonate, mg/kg		0.0	0.0	0.0	0.0
Chloride, mg/kg		470	4800	510	1800
Ammonia Nitrogen (as N), mg/kg		6.6	8.4	10	500
Sulfate, mg/kg		67	67	50	2000

  
Edward Wilson, Laboratory Director

B-8

RECEIVED

AUG 06 1985



BROWN AND CALDWELL

ANALYTICAL LABORATORIES

JHK &amp; A LA

LOG NO: P85-07-415

Received: 09 JUL 85

Reported: 31 JUL 85

Ken Durand  
J.H. Kleinfelder & Assoc.  
901 W. Victoria St., Suite G  
Compton, CA 90220

Project: Q1014-2

## REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES					DATE SAMPLED	
07-415-1	B1-40 Q-1014-2					08 JUL 85	
07-415-2	B1-50 Q-1014-2					08 JUL 85	
07-415-3	B2-35 Q-1014-2					08 JUL 85	
07-415-4	B2-40 Q-1014-2					08 JUL 85	
07-415-5	B3-15 Q-1014-2					08 JUL 85	
07-415-6	B4-10 Q-1014-2					08 JUL 85	
PARAMETER	07-415-1	07-415-2	07-415-3	07-415-4	07-415-5	07-415-6	
H, Units	3.9	5.5	3.3	3.8	6.3	4.0	

B-9

LOG NO: P85-07-415

Received: 09 JUL 85

Reported: 31 JUL 85

Ken Durand  
J.H. Kleinfelder & Assoc.  
901 W. Victoria St., Suite G  
Compton, CA 90220

Project: Q1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES	DATE SAMPLED
7-415-7	B4-25 Q-1014-2	08 JUL 85
07-415-8	S-07-35 Q-1014-2	08 JUL 85
07-415-9	S-11-10 Q-1014-2	09 JUL 85
7-415-10	S-11-35 Q-1014-2	09 JUL 85
07-415-11	B5-10 Q-1014-2	12 JUL 85
07-415-12	B5-25 Q-1014-2	12 JUL 85

PARAMETER	07-415-7	07-415-8	07-415-9	07-415-10	07-415-11	07-415-12
H, Units	4.2	6.9	4.9	8.2	8.3	4.5

B-10

LOG NO: P85-07-415

Received: 09 JUL 85

Reported: 31 JUL 85

Ken Durand  
J.H. Kleinfelder & Assoc.  
901 W. Victoria St., Suite G  
Compton, CA 90220

Project: Q1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES	DATE SAMPLED
07-415-13	B6-15 Q-1014-2	12 JUL 85
07-415-14	B6-25 Q-1014-2	12 JUL 85
07-415-15	S-4A-10 Q-1014-2	12 JUL 85
07-415-16	S-4A-25 Q-1014-2	12 JUL 85
07-415-17	S-08-10 Q-1014-2	12 JUL 85
07-415-18	S-08-25 Q-1014-2	12 JUL 85

PARAMETER	07-415-13	07-415-14	07-415-15	07-415-16	07-415-17	07-415-18
H, Units	3.6	4.2	4.9	6.2	7.3	8.5

B-11

LOG NO: P85-07-415

Received: 09 JUL 85

Reported: 31 JUL 85

Ken Durand  
J.H. Kleinfelder & Assoc.  
901 W. Victoria St., Suite G  
Compton, CA 90220


Project: Q1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES	DATE SAMPLED
07-415-19	S-09-15 Q-1014-2	12 JUL 85
07-415-20	S-09-25 Q-1014-2	12 JUL 85
07-415-21	S-10-10 Q-1014-2	12 JUL 85
07-415-22	S-10-25 Q-1014-2	12 JUL 85

PARAMETER	07-415-19	07-415-20	07-415-21	07-415-22
pH, Units	6.9	7.4	8.3	7.3

  
Edward Wilson, Laboratory Director

B-12



AUG 01 1985

JHK &amp; A LA

BROWN AND CALDWELL



ANALYTICAL LABORATORIES

LOG NO: P85-07-169

Received: 10 JUL 85

Reported: 30 JUL 85

Ken Durand  
 J.H. Kleinfelder & Assoc.  
 901 W. Victoria St., Suite G  
 Compton, CA 90220

Project: Q1014-2

## REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES					DATE SAMPLED
7-169-1	B1-40 Q1014-2					08 JUL 85
07-169-2	B1-50 Q1014-2					08 JUL 85
07-169-3	B2-35 Q1014-2					08 JUL 85
7-169-4	B2-40 Q1014-2					08 JUL 85
07-169-5	B3-15 Q1014-2					08 JUL 85
07-169-6	B4-10 Q1014-2					08 JUL 85
PARAMETER	07-169-1	07-169-2	07-169-3	07-169-4	07-169-5	07-169-6
Cadmium, mg/kg	1.5	8.0	1.2	1.4	<0.67	<0.62
Chromium, mg/kg	600	280	2000	150	16	16,000
Copper, mg/kg	400	160	250	550	31	820
Zinc, mg/kg	180	95	120	170	57	92
Nitric Acid Digestion, Date	07/11/85	07/11/85	07/11/85	07/11/85	07/11/85	07/11/85

B-13

LOG NO: P85-07-169

Received: 10 JUL 85

Reported: 30 JUL 85

Ken Durand  
J.H. Kleinfelder & Assoc.  
901 W. Victoria St., Suite G  
Compton, CA 90220

Project: Q1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES	DATE SAMPLED			
07-169-7	B4-25 Q1014-2	08 JUL 85			
07-169-8	S-07-35 Q1014-2	08 JUL 85			
07-169-9	S-11-10 Q1014-2	09 JUL 85			
07-169-10	S-11-35 Q1014-2	09 JUL 85			
PARAMETER		07-169-7	07-169-8	07-169-9	07-169-10
Cadmium, mg/kg		<0.61	<0.59	1.2	3.0
Chromium, mg/kg		550	35	16	18
Copper, mg/kg		1200	46	2400	40
Zinc, mg/kg		52	77	120	68
Nitric Acid Digestion, Date		07/11/85	07/11/85	07/11/85	07/11/85

B-14

LOG NO: P85-07-169

Received: 10 JUL 85

Reported: 30 JUL 85

Ken Durand  
J.H. Kleinfelder & Assoc.  
901 W. Victoria St., Suite G  
Compton, CA 90220

Project: Q1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES	DATE SAMPLED
7-169-11	B4-15 Q1014-2	08 JUL 85
PARAMETER	07-169-11	
Purgeable Priority Pollutants		
Extraction	07/27/85	
Acrolein, mg/kg	<3	
Acrylonitrile, mg/kg	<3	
Other Purgeable Priority Pollutants,	<0.3	

B-15

LOG NO: P85-07-169

Received: 10 JUL 85

Reported: 30 JUL 85

Ken Durand  
J.H. Kleinfelder & Assoc.  
901 W. Victoria St., Suite G  
Compton, CA 90220

Project: Q1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES	DATE SAMPLED
0 -169-12	B1-05 Q1014-2	08 JUL 85
0 -169-13	B1-10 Q1014-2	08 JUL 85
07-169-14	B1-15 Q1014-2	08 JUL 85
07-169-15	B1-20 Q1014-2	08 JUL 85
0 -169-16	B1-30 Q1014-2	08 JUL 85
07-169-17	B2-05 Q1014-2	08 JUL 85

PARAMETER	07-169-12	07-169-13	07-169-14	07-169-15	07-169-16	07-169-17
Sample Held, Not Analyzed	HOLD	HOLD	HOLD	HOLD	HOLD	HOLD

B-16

LOG NO: P85-07-169

Received: 10 JUL 85

Reported: 30 JUL 85

Ken Durand  
J.H. Kleinfelder & Assoc.  
901 W. Victoria St., Suite G  
Compton, CA 90220

Project: Q1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES	DATE SAMPLED
07-169-18	B2-10 Q1014-2	08 JUL 85
07-169-19	B2-15 Q1014-2	08 JUL 85
07-169-20	B2-20 Q1014-2	08 JUL 85
07-169-21	B2-30 Q1014-2	08 JUL 85
07-169-22	B3-05 Q1014-2	08 JUL 85
07-169-23	B3-10 Q1014-2	08 JUL 85

PARAMETER	07-169-18	07-169-19	07-169-20	07-169-21	07-169-22	07-169-23
Sample Held, Not Analyzed	HOLD	HOLD	HOLD	HOLD	HOLD	HOLD

B-17

LOG NO: P85-07-169

Received: 10 JUL 85

Reported: 30 JUL 85

Ken Durand  
J.H. Kleinfelder & Assoc.  
901 W. Victoria St., Suite G  
Compton, CA 90220

Project: Q1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES	DATE SAMPLED
7-169-24	B4-05 Q1014-2	08 JUL 85
7-169-25	B4-20 Q1014-2	08 JUL 85
07-169-26	B4-30 Q1014-2	08 JUL 85
7-169-27	S-07-05 Q1014-2	08 JUL 85
7-169-28	S-07-15 Q1014-2	08 JUL 85
07-169-29	S-07-20 Q1014-2	08 JUL 85

PARAMETER	07-169-24	07-169-25	07-169-26	07-169-27	07-169-28	07-169-29
Sample Held, Not Analyzed	HOLD	HOLD	HOLD	HOLD	HOLD	HOLD

B-18

LOG NO: P85-07-169

Received: 10 JUL 85

Reported: 30 JUL 85

Ken Durand  
J.H. Kleinfelder & Assoc.  
901 W. Victoria St., Suite G  
Compton, CA 90220


Project: Q1014-2

REPORT OF ANALYTICAL RESULTS

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES	DATE SAMPLED
7-169-30	S-07-25 Q1014-2	08 JUL 85
7-169-31	S-07-45 Q1014-2	08 JUL 85
07-169-32	S-11-05 Q1014-2	09 JUL 85
7-169-33	S-11-15 Q1014-2	09 JUL 85
7-169-34	S-11-25 Q1014-2	09 JUL 85
07-169-35	S-11-45 Q1014-2	09 JUL 85

PARAMETER	07-169-30	07-169-31	07-169-32	07-169-33	07-169-34	07-169-35
Sample Held, Not Analyzed	HOLD	HOLD	HOLD	HOLD	HOLD	HOLD

  
Edward Wilson, Laboratory Director

B-19

# Soil sample

Southern California Chemical Lab.

7/9/85  
G. Otterbach.  
T. King.  
page 1 of 3

		ppm Cr	ppm Cu	ppm Cd	
1.	B3-15'	7,000	3,583	nil	pH 7.02 sand
2.	B4-05'	23,000	2,666	nil	pH 3.78 silt &.
3.	B4-10'	17,500	692	nil	pH-3.38 silt
4.	B4-15'	11,250	4,333	nil	pH 3.58 silt
5.	B4-20'	4,000	1,750	nil	pH 3.68 sand
6.	B4-25'	283	1,333	nil	pH 4.07 sand
7.	B4-30'	5,416	2,416	nil	pH.3.38 silt & sand
8.	B1-40'	616	266	4.8ppm	pH 3.61 silt
9.	B1-50'	192	46	5.8	pH 6.08 clay.
10.	B2-35'	1,333	142	4.8	pH 3.10 silt
11.	B2-40'	583	308	4.8	pH 3.26 clay B-20
12.	B1-05'	50	150	4.2	pH 6.57. sand.



		Cu ppm	Cu ppm	Cd ppm		
13	MW8-05	1,417	192	nil	pH 7.44	silt
14	MW8-10	4.2	58	nil	pH 6.03	silt & clay
15	MW8-15	192	92	nil	pH 6.51	sand
16	MW8-20	8.3	33	nil	pH 5.58	sand
17	MW8-25	nil	17	nil	pH 6.16	sand
18	MW8-35	25	42	nil	pH 5.99	clay.
19	B5-05	1,500	1,583	nil	pH 3.72	silt sand
20	B5-10	25	58	nil	pH 6.91	silt
21	B5-15	1,083	2,333	nil	pH 6.62	silt
22	B5-20	1,416	1,666	nil	pH 5.25	silt
23	B5-25	283	450	nil	pH 3.70	sand
24	B5-30	233	675	nil	pH 3.98	sand.
25	B6-05	30,000	13,333	nil	pH 6.62	B-21, silt & clay

[illegible]

J. H. KLEINFELDER & ASSOCIATES

APPENDIX C

# CHAIN OF CUSTODY RECEIPT

SAMPLERS: (Signature)

*[Signature]*

Phone: \_\_\_\_\_

SHIP TO:

*Brown & Caldwell*

ATTENTION: \_\_\_\_\_

Phone No. \_\_\_\_\_

## SHIPPING INFORMATION

Shipper \_\_\_\_\_

Address \_\_\_\_\_

Date Shipped \_\_\_\_\_

Shipment Service \_\_\_\_\_

Airbill No. \_\_\_\_\_

Cooler No. \_\_\_\_\_

Relinquished by: (Signature)

*[Signature]*

Received by: (Signature)

*[Signature]*

Date/Time

7/10/85 1:42 PM

Relinquished by: (Signature)

*[Signature]*

Received by: (Signature)

*[Signature]*

Date/Time

7/10/85 3:42 AM

Relinquished by: (Signature)

Received by: (Signature)

Date/Time

Relinquished by: (Signature)

Receive for laboratory by: (Signature)

Date/Time

\*Analysis laboratory should complete, "sample condition upon receipt", section below, sign and return original (white) copy to J. H. KLEINFELDER & ASSOCIATES, 901 W. Victoria Street, Suite G, Compton, CA 90220.

Sample Number	Site Identification	Date Sampled	Analysis Requested	Sample Condition Upon Receipt
2- B3-05	Q1014-2	7-8-85	hold	
2- B3-10			hold	
5- B3-15			Same 4 metals	
24 B4-05			hold	
6- B4-10			Same 4 metals	
11 B4-15			hold	
25 B4-20			hold	
7 B4-25			Same 4 metals	
2 B4-30			hold	
27 S-07-05			hold	
28 S-07-15			<del>hold</del>	
29 S-07-20			hold	
30 S-07-25			hold	
8 S-07-35			Same 4 metals	

LAB INSTRUCTIONS: Laboratory reports should reference and be billed by site ID# and contain the following:

- summary of analytical methodology and QA work (blanks, spikes, duplicates)
- dates for (a) sampling, (b) lab receipt, (c) extraction, (d) injection/analysis
- detection limits for all constituents analyzed for and reporting of all constituents detected which were not specifically designated

# CHAIN OF CUSTODY RECEIPT

85-07-169

SAMPLERS: (Signature)

*[Signature]*

Phone: \_\_\_\_\_

SHIP TO:

*Brown & Caldwell*

ATTENTION: \_\_\_\_\_

Phone No. \_\_\_\_\_

## SHIPPING INFORMATION

Shipper \_\_\_\_\_

Address \_\_\_\_\_

Date Shipped \_\_\_\_\_

Shipment Service \_\_\_\_\_

Airbill No. \_\_\_\_\_

Cooler No. \_\_\_\_\_

Relinquished by: (Signature)

*[Signature]*

Received by: (Signature)

*[Signature]*

Date/Time

7/10/85 1142

Relinquished by: (Signature)

*[Signature]*

Received by: (Signature)

*[Signature]*

Date/Time

7/10/85 3:42 PM

Relinquished by: (Signature)

Received by: (Signature)

Date/Time

Relinquished by: (Signature)

Receive for laboratory by: (Signature)

Date/Time

\*Analysis laboratory should complete, "sample condition upon receipt", section below, sign and return original (white) copy to J. H. KLEINFELDER & ASSOCIATES, 901 W. Victoria Street, Suite G, Compton, CA 90220.

Sample Number	Site Identification	Date Sampled	Analysis Requested	Sample Condition Upon Receipt
12 B1-05	G 1014-2	7-8-85	hold	
13 B1-10			hold	
14 B1-15			hold	
15 B1-20			hold	
16 B1-35			hold	
1 B1-40			Cadmium, Chromium, Zinc, Copper	
2 B1-50			Same 4 metals	
17 B2-05			hold	
18 B2-10			hold	
19 B2-15			hold	
20 B2-20			hold	
21 B2-30			hold	
3 B2-35			Same 4 metals	
4 B2-40			" " "	

LAB INSTRUCTIONS: Laboratory reports should reference and be billed by site ID# and contain the following:

- (1) summary of analytical methodology and QA work (blanks, spikes, duplicates)
- (2) dates for (a) sampling, (b) lab receipt, (c) extraction, (d) injection/analysis
- (3) detection limits for all constituents analyzed for and reporting of all constituents detected which were not specifically designated

# CHAIN OF CUSTODY RECORD

AMPLERS: (Signature)

Phone: (213) 638-9344

SHIP TO:

Brown - Caldwell

ATTENTION:

Phone No.

## SHIPPING INFORMATION

Shipper

BEC

Address

Date Shipped

Shipment Service

Airbill No.

Cooler No.

Relinquished by: (Signature)

Received by: (Signature)

Date/Time

Relinquished by: (Signature)

Received by: (Signature)

Date/Time

Relinquished by: (Signature)

Received by: (Signature)

Date/Time

Relinquished by: (Signature)

Receive for laboratory by: (Signature)

Date/Time

\*Analysis laboratory should complete, "sample condition upon receipt", section below, sign and return original (white) copy to J. H. KLEINFELDER & ASSOCIATES, 901 W. Victoria Street, Suite G, Compton, CA 90220.

Sample Number	Site Identification	Date Sampled	Analysis Requested	Sample Condition Upon Receipt
✓ B5-05	Q10142	7-11-85	hold	
✓ 35-10 1			Copper, Chromium, Nickel zinc	
✓ B5-15			hold	
✓ 35-20			hold	
✓ B5-25 2			Copper, Chromium Nickel zinc	
✓ 35-30			hold	
✓ B6-05			hold	
✓ 6-15 3			same as above	
✓ B6-20			hold	
✓ 36-25 4			same as above	
✓ B6-30			hold	

LA INSTRUCTIONS: Laboratory reports should reference and be billed by site ID# and contain the following:

- summary of analytical methodology and QA work (blanks, spikes, duplicates)
- dates for (a) sampling, (b) lab receipt, (c) extraction, (d) injection/analysis
- detection limits for all constituents analyzed for and reporting of all constituents detected which were not specifically designated

(4)  
(5)

# CHAIN OF CUSTODY RECORD

85-07-211

SAMPLERS: (Signature)

*Kris Duenkel*

Phone: (613) 638-9344

HIPTO:

*Brown & Caldwell*

ATTENTION:

Phone No.

## SHIPPING INFORMATION

Shipper

*BCC*

Address

Date Shipped

Shipment Service

Airbill No.

Cooler No.

Relinquished by: (Signature)

*Kris Duenkel*

Received by: (Signature)

*Charles Holmes*

Date/Time

*7/12/85 4:55*

Relinquished by: (Signature)

*Charles Holmes*

Received by: (Signature)

Date/Time

Relinquished by: (Signature)

Received by: (Signature)

Date/Time

Relinquished by: (Signature)

Receive for laboratory by: (Signature)

Date/Time

\*Analysis laboratory should complete, "sample condition upon receipt", section below, sign and return original (white) copy to J. H. KLEINFELDER & ASSOCIATES, 901 W. Victoria Street, Suite G, Compton, CA 90220.

Sample Number	Site Identification	Date Sampled	Analysis Requested	Sample Condition Upon Receipt
3-4A-05 ✓	Q1014-2	7-10-85	hold	
5-4A-10 ✓			Copper, Chromium, Zinc, Nickel	
3-4A-15 ✓			hold	
3-4A-20 ✓			hold	
6-4A-25 ✓			Same as Above	
3-4A-35 ✓			hold	
3-08-05 ✓			hold	
7-08-10 ✓			Same as Above	
3-08-15 ✓			hold	
3-08-20 ✓			hold	
8-08-25 ✓			Same as Above	
3-08-35 ✓			hold	

LAB INSTRUCTIONS: Laboratory reports should reference and be billed by site ID# and contain the following:

- (1) summary of analytical methodology and QA work (blanks, spikes, duplicates)
- (2) dates for (a) sampling, (b) lab receipt, (c) extraction, (d) injection/analysis
- (3) detection limits for all constituents analyzed for and reporting of all constituents detected which were not specifically designated
- (4)
- (5)

# CHAIN OF CUSTODY RECORD

SAMPLERS: (Signature)

Ken [Signature]

Phone: (213) 638-9344

SHIP TO:

Brown & Caldwell

ATTENTION:

Phone No. \_\_\_\_\_

## SHIPPING INFORMATION

Shipper B & C.

Address \_\_\_\_\_

Date Shipped \_\_\_\_\_

Shipment Service \_\_\_\_\_

Airbill No. \_\_\_\_\_

Cooler No. \_\_\_\_\_

Relinquished by: (Signature)

Ken [Signature]

Received by: (Signature)

[Signature]

Date/Time

7/12/85 4:00

Relinquished by: (Signature)

[Signature]

Received by: (Signature)

Date/Time

Relinquished by: (Signature)

Received by: (Signature)

Date/Time

Relinquished by: (Signature)

Receive for laboratory by: (Signature)

Date/Time

\*Analysis laboratory should complete, "sample condition upon receipt", section below, sign and return original (white) copy to J. H. KLEINFELDER & ASSOCIATES, 901 W. Victoria Street, Suite G, Compton, CA 90220.

Sample Number	Site Identification	Date Sampled	Analysis Requested	Sample Condition Upon Receipt
✓ S-09-05	Q 10142	7-12-85	hold	
✓ S-09-159			Copper, Chromium, Nickel, Zinc	
✓ S-09-20			hold	
✓ S-09-25 10			same as above	
✓ S-09-35			hold	
✓ S-10-05			hold	
✓ S-10-10 11			same as above	
✓ S-10-15			hold	
✓ S-10-20			hold	
✓ S-10-25 12			same as above	
✓ S-10-45			hold	

LAB INSTRUCTIONS: Laboratory reports should reference and be billed by site ID# and contain the following:

- 1) summary of analytical methodology and QA work (blanks, spikes, duplicates)
- 2) dates for (a) sampling, (b) lab receipt, (c) extraction, (d) injection/analysis
- 3) detection limits for all constituents analyzed for and reporting of all constituents detected which were not specifically designated





# CHAIN OF CUSTODY RECORD

SAMPLERS: (Signature)

Phone:

SHIP TO:

ATTENTION:

Phone No.

## SHIPPING INFORMATION

Shipper

Address

Date Shipped

Shipment Service

Airbill No.

Cooler No.

Relinquished by: (Signature)

Received by: (Signature)

Date/Time

Relinquished by: (Signature)

Received by: (Signature)

Date/Time

Relinquished by: (Signature)

Received by: (Signature)

Date/Time

Relinquished by: (Signature)

Receive for laboratory by: (Signature)

Date/Time

\*Analysis laboratory should complete, "sample condition upon receipt", section below, sign and return original (white) copy to J. H. KLEINFELDER & ASSOCIATES, 901 W. Victoria Street, Suite G, Compton, CA 90220.

Sample Number	Site Identification	Date Sampled	Analysis Requested	Sample Condition Upon Receipt
B1-05	G 174-2	7-9-85	Gold	
B1-10			Gold	
B1-15			Gold	
B1-20			Gold	
B1-30			Gold	
B1-40			Chromium, Chromium Dioxide, Copper	
B1-50			Same 4 metals	
B2-05			Gold	
B2-10			Gold	
B2-15			Gold	
B2-20			Gold	
B2-30			Gold	
B2-35			Same 4 metals	
B2-40	V	V		

LAB INSTRUCTIONS: Laboratory reports should reference and be billed by site ID# and contain the following:

- ( summary of analytical methodology and QA work (blanks, spikes, duplicates)
- ( dates for (a) sampling, (b) lab receipt, (c) extraction, (d) injection/analysis
- ( detection limits for all constituents analyzed for and reporting of all constituents detected which were not specifically designated

# CHAIN OF CUSTODY RECORD

SAMPLERS: (Signature)

Phone:

SHIP TO:

ATTENTION:

Phone No.

## SHIPPING INFORMATION

Shipper

Address

Date Shipped

Shipment Service

Airbill No.

Cooler No.

Relinquished by: (Signature)

Received by: (Signature)

Date/Time

Relinquished by: (Signature)

Received by: (Signature)

Date/Time

Relinquished by: (Signature)

Received by: (Signature)

Date/Time

Relinquished by: (Signature)

Receive for laboratory by\*: (Signature)

Date/Time

\*Analysis laboratory should complete, "sample condition upon receipt", section below, sign and return original (white) copy to J. H. KLEINFELDER & ASSOCIATES, 901 W. Victoria Street, Suite G, Compton, CA 90220.

Sample Number	Site Identification	Date Sampled	Analysis Requested	Sample Condition Upon Receipt
B3-05	1114-2	7-5-85	hold	
B3-10			hold	
B3-15			Same 4 methods	
B4-05			hold	
B4-10			Same 4 methods	
B4-15			hold	
B4-20			hold	
B4-25			Same 4 methods	
B4-30			hold	
S-07-05			hold	
S-07-15			hold	
S-07-20			hold	
S-07-25			hold	
S-07-30			Same 4 methods	

LAB INSTRUCTIONS: Laboratory reports should reference and be billed by site ID# and contain the following:

- 1) summary of analytical methodology and QA work (blanks, spikes, duplicates)
- 2) dates for (a) sampling, (b) lab receipt, (c) extraction, (d) injection/analysis
- 3) detection limits for all constituents analyzed for and reporting of all constituents detected which were not specifically designated
- 4)
- 5)

# CHAIN OF CUSTODY RECORD

SAMPLERS: (Signature)

*Mark Eblum*

Phone:

SHIP TO:

*Brown & Caldwell*

*Pasadena*

ATTENTION:

Phone No.

## SHIPPING INFORMATION

Shipper

Address

Date Shipped

Shipment Service

Airbill No.

Cooler No.

Relinquished by: (Signature)

*Mark Eblum*

Received by: (Signature)

*Holden Kneeling*

Date/Time

*7/24/85 4:39*

Relinquished by: (Signature)

Received by: (Signature)

Date/Time

Relinquished by: (Signature)

Received by: (Signature)

Date/Time

Relinquished by: (Signature)

Receive for laboratory by\*: (Signature)

Date/Time

\*Analysis laboratory should complete, "sample condition upon receipt", section below, sign and return original (white) copy to J. H. KLEINFELDER & ASSOCIATES, 901 W. Victoria Street, Suite G, Compton, CA 90220.

Sample Number	Site Identification	Date Sampled	Analysis Requested	Sample Condition Upon Receipt
<i>60-00-137</i>	<i>Q-1014-2</i>	<i>7/24/85</i>	<i>EPA method 624</i>	
<i>60-00-138</i>				
<i>60-02-140</i>			<i>EPA method 624</i>	
<i>60-02-142</i>			<i>chromium</i>	
<i>60-05-144</i>			<i>EPA method 624</i>	
<i>60-05-145</i>				
<i>60-04-146</i>			<i>EPA method 624</i>	
<i>60-04-147</i>				
<i>60-04-148</i>			<i>chromium method 624</i>	
<i>60-03-149</i>			<i>EPA method 624</i>	
<i>60-00-150</i>				
<i>60-03-152</i>			<i>EPA method 624</i>	
<i>60-03-153</i>				
<i>60-03-154</i>			<i>chromium, cadmium</i>	

LAB INSTRUCTIONS: Laboratory reports should reference and be billed by site ID# and contain the following:

- summary of analytical methodology and QA work (blanks, spikes, duplicates)
- dates for (a) sampling, (b) lab receipt, (c) extraction, (d) injection/analysis
- detection limits for all constituents analyzed for and reporting of all constituents detected which were not specifically designated

(4) *For all samples analyzed by method 624 on 7/24/85, detection limits*

# CHAIN OF CUSTODY RECEIPT

SAMPLERS: (Signature)

*Mark Field*

Phone: 638 9344

SHIP TO:

Brown & Caldwell

373 Fair Oaks

Pasadena Ca 91105

ATTENTION: Joyce

Phone No. \_\_\_\_\_

## SHIPPING INFORMATION

Shipper JHK&A

Address \_\_\_\_\_

Date Shipped 2 AUGUST 85

Shipment Service BIC COURIER

Airbill No. \_\_\_\_\_

Cooler No. #3

Relinquished by: (Signature)

*Mark Field*

Received by: (Signature)

*[Signature]*

Date/Time

8-28-85 5:25

Relinquished by: (Signature)

Received by: (Signature)

Date/Time

Relinquished by: (Signature)

Received by: (Signature)

Date/Time

Relinquished by: (Signature)

Receive for laboratory by: (Signature)

Date/Time

\*Analysis laboratory should complete, "sample condition upon receipt", section below, sign and return top copy to J. H. KLEINFELDER & ASSOCIATES, 15303 Ventura Blvd., Suite 700, Sherman Oaks, CA 91403-3156.

Sample Number	Site Identification	Date Sampled	Analysis Requested	Sample Condition Upon Receipt
<u>2-00-155</u>	<u>Q-1014-2</u>	<u>8/2/85</u>	<u>TOX</u>	
<u>1-00-156</u>	<u>/</u>	<u>/</u>		
<u>2-00-157</u>	<u>/</u>	<u>/</u>		
<u>11-00-158</u>	<u>/</u>	<u>/</u>		
<u>1-07-159</u>	<u>/</u>	<u>/</u>	<u>TOX</u>	
<u>1-07-160</u>	<u>/</u>	<u>/</u>	<u>TOX</u>	
<u>2-07-161</u>	<u>/</u>	<u>/</u>	<u>TOX</u>	
<u>11-07-162</u>	<u>/</u>	<u>/</u>	<u>TOX</u>	
<u>2-07-163</u>	<u>/</u>	<u>/</u>	<u>TOX</u>	
<u>2-07-164</u>	<u>/</u>	<u>/</u>	<u>TOX</u>	
<u>1-07-165</u>	<u>/</u>	<u>/</u>	<u>TOX</u>	
<u>2-07-166</u>	<u>/</u>	<u>/</u>	<u>TOX</u>	
<u>11-07-167</u>	<u>/</u>	<u>/</u>	<u>TOX</u>	
<u>2-07-168</u>	<u>/</u>	<u>/</u>	<u>TOX</u>	

LAB INSTRUCTIONS: Laboratory reports should reference and be billed by site ID# and contain the following:

- ( ) summary of analytical methodology and QA work (blanks, spikes, duplicates)
- ( ) dates for (a) sampling, (b) lab receipt, (c) extraction, (d) injection/analysis
- (3) detection limits for all constituents analyzed for and reporting of all constituents detected which were not specifically designated

# CHAIN OF CUSTODY RECORD

SAMPLERS: (Signature)

*Mark Clark*

Phone: 638 9344

SHIP TO:

*Brown & Caldwell*

*373 FAIROAKS*

*Pasadena CA 91105*

ATTENTION: *JOYCE*

Phone No.

## SHIPPING INFORMATION

Shipper

*JHK LH*

Address

Date Shipped

*2 AUGUST 85*

Shipment Service

*BIC COURIER*

Airbill No.

Cooler No.

*#3*

Relinquished by: (Signature)

*Mark Clark*

Received by: (Signature)

*Mark Clark*

Date/Time

*2:16 5:30*

Relinquished by: (Signature)

Received by: (Signature)

Date/Time

Relinquished by: (Signature)

Received by: (Signature)

Date/Time

Relinquished by: (Signature)

Receive for laboratory by\*: (Signature)

Date/Time

\*Analysis laboratory should complete, "sample condition upon receipt", section below, sign and return top copy to J. H. KLEINFELDER & ASSOCIATES, 15303 Ventura Blvd., Suite 700, Sherman Oaks, CA 91403-3156.

Sample Number	Site Identification	Date Sampled	Analysis Requested	Sample Condition Upon Receipt
<i>W-07-169</i>	<i>Q-1014-2</i>	<i>8/2/85</i>	<i>1st run</i>	
<i>W-07-170</i>			<i>2nd run</i>	
<i>W-07-171</i>			<i>1st run</i>	
<i>W-07-172</i>			<i>1st run</i>	
<i>W-07-173</i>			<i>1st run</i>	
<i>W-11-174</i>			<i>TOC</i>	
<i>W-11-175</i>			<i>TOC</i>	
<i>W-11-176</i>			<i>TOC</i>	
<i>W-11-177</i>			<i>TOC</i>	
<i>W-11-178</i>			<i>TOC</i>	
<i>W-11-179</i>			<i>TOC</i>	
<i>W-11-180</i>			<i>TOC</i>	
<i>W-11-181</i>			<i>TOC</i>	
<i>W-11-182</i>			<i>TOC</i>	

LAB INSTRUCTIONS: Laboratory reports should reference and be billed by site ID# and contain the following:

- summary of analytical methodology and QA work (blanks, spikes, duplicates)
- dates for (a) sampling, (b) lab receipt, (c) extraction, (d) injection/analysis
- detection limits for all constituents analyzed for and reporting of all constituents detected which were not specifically designated
- 
-

# CHAIN OF CUSTODY RECORD

**SAMPLERS:** (Signature) Mark F. Hall

**Phone:** 638 9344

**SHIP TO:**

Brown & Caldwell

373 FAIROAKS

Pasadena CA 91105

**ATTENTION:** Joyce

**Phone No.** \_\_\_\_\_

## SHIPPING INFORMATION

**Shipper** JHK LH

**Address** \_\_\_\_\_

**Date Shipped** 2 AUGUST 85

**Shipment Service** BIC COURIER

**Airbill No.** \_\_\_\_\_

**Cooler No.** # 3

Relinquished by: (Signature) <u>Mark F. Hall</u>	Received by: (Signature) <u>[Signature]</u>	Date/Time <u>8/2/85</u>
Relinquished by: (Signature) _____	Received by: (Signature) _____	Date/Time _____
Relinquished by: (Signature) _____	Received by: (Signature) _____	Date/Time _____
Relinquished by: (Signature) _____	Received by: (Signature) _____	Date/Time _____

\*Analysis laboratory should complete, "sample condition upon receipt", section below, sign and return top copy to J. H. KLEINFELDER & ASSOCIATES, 15303 Ventura Blvd., Suite 700, Sherman Oaks, CA 91403-3156.

Sample Number	Site Identification	Date Sampled	Analysis Requested	Sample Condition Upon Receipt
<u>W-11-183</u>	<u>Q-1014-2</u>	<u>8/2/85</u>	<u>Cont. Catb</u>	
<u>W-11-184</u>			<u>all</u>	
<u>W-11-185</u>			<u>all</u>	
<u>W-11-186</u>			<u>all</u>	
<u>W-11-187</u>			<u>all</u>	
<u>W-11-188</u>			<u>C-6 C1</u>	
<u>W-09-189</u>			<u>TCC</u>	
<u>W-09-190</u>			<u>TCC</u>	
<u>W-09-191</u>			<u>TCC</u>	
<u>W-09-192</u>			<u>TCC</u>	
<u>W-09-193</u>			<u>TCC</u>	
<u>W-09-194</u>			<u>TCC</u>	
<u>W-09-195</u>			<u>TCC</u>	
<u>W-09-196</u>			<u>TCC</u>	

**LAB INSTRUCTIONS:** Laboratory reports should reference and be billed by site ID# and contain the following:

- summary of analytical methodology and QA work (blanks, spikes, duplicates)
- dates for (a) sampling, (b) lab receipt, (c) extraction, (d) injection/analysis
- detection limits for all constituents analyzed for and reporting of all constituents detected which were not specifically designated

4) \_\_\_\_\_

5) \_\_\_\_\_





J. H. KLEINFELDER & ASSOCIATES

APPENDIX D



See reverse side for instructions.  
Please print clearly. Press Hard.

State Department of Health Services  
HAZARDOUS MATERIALS MANAGEMENT SECTION  
744 P Street, Sacramento, CA 95814

1 Manifest Number **189 000452**

**GENERATOR**

(GENERATOR MUST COMPLETE)

3 Designated TSD Facility (Authorized to operate under an approved state program or federal program.)

4 Alternate TSD Facility

2 Name **SOUTHERN CALIF CHEM**  
EPA # **CA 0008488025**  
Address **8851 DICE RD** Phone **698-8036**  
City, State, Zip **S.F.S. CA 90670**

Name **BKK**  
EPA # **CA 0067786749**  
Address **2210 AZUSA RD** Phone **965-0916**  
City, State, Zip **WEST COVINA CA**

Name \_\_\_\_\_  
EPA # \_\_\_\_\_  
Address \_\_\_\_\_ Phone \_\_\_\_\_  
City, State, Zip \_\_\_\_\_

5 U.S. DOT PROPER SHIPPING NAME	U.S. DOT HAZARD CLASS	UN/NA ID NO.	WEIGHT OR VOLUME	UNITS	NUMBER OF CONTAINERS
WASTE <b>N/A</b>			<b>5.000</b>	<b>GALS</b>	
WASTE					TYPE: <input type="checkbox"/> DRUMS <input type="checkbox"/> BAGS <input type="checkbox"/> CARTONS <input checked="" type="checkbox"/> TANK TRUCK <input type="checkbox"/> DUMP TRUCK <input type="checkbox"/> OTHER

6 Waste Category **MUD & WATER** 7 Ext. Haz. Waste Permit No. **N/A** 8 Generating Process **METAL RECLAIMING**

LIST COMPONENTS:			CONCENTRATION RANGE	UNITS	LIST COMPONENTS:			CONCENTRATION RANGE	UNITS
			UPPER	LOWER				UPPER	LOWER
9 A.	<b>IRON</b>	<b>25</b>	<b>15</b>	<input checked="" type="checkbox"/> % <input type="checkbox"/> ppm.	E.				<input type="checkbox"/> % <input type="checkbox"/> ppm.
B.	<b>COPPER</b>	<b>5</b>	<b>2</b>	<input checked="" type="checkbox"/> % <input type="checkbox"/> ppm.	F.				<input type="checkbox"/> % <input type="checkbox"/> ppm.
C.	<b>CHROME</b>	<b>3</b>	<b>1</b>	<input checked="" type="checkbox"/> % <input type="checkbox"/> ppm.	G.				<input type="checkbox"/> % <input type="checkbox"/> ppm.
D.	<b>OTHER METALS</b>	<b>1</b>	<b>1</b>	<input checked="" type="checkbox"/> % <input type="checkbox"/> ppm.	Non-Hazardous Material _____ %				

10 WASTE PROPERTIES: pH **7.0** ☐ Toxic ☐ Flammable ☐ Corrosive/Irritant ☐ Reactive ☐ Sensitizer ☐ Carcinogen/Mutagen

11 PHYSICAL STATE: ☐ Solid ☐ Liquid ☒ Sludge ☐ Slurry ☐ Gas ☐ Other

12 SPECIAL HANDLING INSTRUCTIONS: ☒ Gloves ☐ Goggles ☐ Respirator ☐ Other **WASH SPILLS WITH WATER**

GENERATOR CERTIFICATION: This is to certify that the above named materials are properly classified, described, packaged, marked, labeled, and are in proper condition for transportation according to the applicable regulations of the Department of Transportation and EPA.

IN THE EVENT OF A SPILL, CONTACT THE NATIONAL  
RESPONSE CENTER, U.S. COAST GUARD 1-800-424-8802

13 **[Signature]**  
Signature of Authorized Agent and Title

**12-8-81**  
Date Shipped

**TRANSPORTER**

(HAULER MUST COMPLETE)

14 TRANSPORTER NAME **NASH SALVAGE INC.**  
ADDRESS **16211 Placid Drive** PHONE **(213) 941-5117**  
CITY, STATE, ZIP **Whittier, CA 90604**

15 PICK-UP DATE **12-8-81** # **2255**  
EPA NO. **CA 00990802993** Time **12:30** ☐ AM ☒ PM

16 **[Signature]**  
Signature of Authorized Agent and Title

**12-8-81**  
Date

**TSD FACILITY**

(FACILITY-OPERATOR MUST COMPLETE)

17 NAME **BKK** 18 QUANTITY (If Measured) **20.97**  
EPA NO. **CA 0067786749** 19 STATE FEE (If Any) **20.97**  
PHONE NO. **9650911**

20 INDICATE ANY SIGNIFICANT DISCREPANCIES BETWEEN MANIFEST AND SHIPMENT:

**RECEIVED**

**DEC 28 1981**

IF WASTE IS HELD FOR DELIVERY ELSEWHERE, SPECIFY THE DESIGNATED TSD FACILITY:

22 Designated TSD Facility Name **60 SO. CALIF. CHEM. CO.**  
23 **[Signature]**  
Signature of Authorized Agent and Title

21 HANDLING OR DISPOSAL METHOD:

- ☐ Surface Impoundment ☒ Landfill  
☐ Injection Well ☐ Land Treatment  
☐ Treatment (Specify) \_\_\_\_\_  
☐ Recovery or Re-use ☐ Storage/Transfer  
☐ Recycle

EPA NO. **12-8-81**  
Date Accepted

-See reverse side for instructions.  
Please type or print clearly. Press Hard.

State Department of Health Services  
HAZARDOUS MATERIALS MANAGEMENT SECTION  
744 P Street, Sacramento, CA 95814

Manifest Number 189 000883

GENERATOR

(GENERATOR MUST COMPLETE)

3 Designated TSD Facility (Authorized to operate under an approved state program or federal program.)

4 Alternate TSD Facility

2 Name Southern California Chemical Co

Name BKK Dump

EPA # C A D 10 0 18 14 18 18 10 12 15

EPA # C A D 0 6 7 7 18 6 7 4 19

Address 8851 Dice Rd. Phone 698-8036

Address 2210 Azusa Rd. Phone

City, State, Zip Santa Fe Springs, Ca. 90670

City, State, Zip Covina, Ca.

Name

EPA #

Address Phone

City, State, Zip

5 U.S. DOT PROPER SHIPPING NAME N/A	U.S. DOT HAZARD CLASS N/A	UN/NA ID NO.	WEIGHT OR VOLUME 5000	UNITS gal.	NUMBER OF CONTAINERS
WASTE Mud & Water (37)					TYPE: <input checked="" type="checkbox"/> DRUMS <input type="checkbox"/> BAGS <input type="checkbox"/> CARTONS <input checked="" type="checkbox"/> TANK TRUCK <input type="checkbox"/> DUMP TRUCK <input type="checkbox"/> OTHER
WASTE					

6 Waste Category Mud & Water (37)

7 Ext. Haz. Waste Permit No. N/A

8 Generating Process Metal Reclaiming

LIST COMPONENTS:

CONCENTRATION RANGE  
UPPER LOWER

UNITS

9 A. Iron 25 15 % ppm.  
B. Copper 5 2 % ppm.  
C. Chrome 1 .1 % ppm.  
D. Other Metals 1 .1 % ppm.

LIST COMPONENTS:

CONCENTRATION RANGE  
UPPER LOWER

UNITS

E. Water 75 60 % ppm.  
F. % ppm.  
G. % ppm.  
Non-Hazardous Material %

10 WASTE PROPERTIES: pH 8.0-9.0 ☒ Toxic ☐ Flammable ☒ Corrosive/Irritant ☐ Reactive ☐ Sensitizer ☐ Carcinogen/Mutagen

11 PHYSICAL STATE: ☐ Solid ☐ Liquid ☒ Sludge ☒ Slurry ☐ Gas ☐ Other

12 SPECIAL HANDLING INSTRUCTIONS: ☒ Gloves ☒ Goggles ☐ Respirator ☐ Other

GENERATOR CERTIFICATION: This is to certify that the above named materials are properly classified, described, packaged, marked, labeled, and are in proper condition for transportation according to the applicable regulations of the Department of Transportation and EPA.

IN THE EVENT OF A SPILL, CONTACT THE NATIONAL  
RESPONSE CENTER, U.S. COAST GUARD 1-800-424-8802

13 Signature of Authorized Agent and Title G. G. Otterbach, Plant Manager  
10-13-82

TRANSPORTER

(HAULER MUST COMPLETE)

14 TRANSPORTER NAME NASH SALVAGE INC.

ADDRESS 16211 Placid Drive

PHONE (213) 941-5117

CITY, STATE, ZIP Whittier, CA 90604

15 PICK-UP DATE 10-13-82 2:06

EPA NO. C A D 9 9 0 8 0 2 9 9 3 Time 11 AM PM

16 Signature of Authorized Agent and Title Robert M. Donnell Driver  
Date 10-13-82

TSD FACILITY

(FACILITY OPERATOR MUST COMPLETE)

17 NAME BKK

EPA NO. C A D 0 6 7 7 18 6 7 4 19

PHONE NO.

18 QUANTITY (If Measured) 23.71

19 STATE FEE (If Any) 94.84

21 HANDLING OR DISPOSAL METHOD:

☐ Surface Impoundment ☒ Landfill

☐ Injection Well ☐ Land Treatment

☐ Treatment (Specify)

☐ Recovery or Re-use ☐ Storage/Transfer

☐ Recycle

20 INDICATE ANY SIGNIFICANT DISCREPANCIES BETWEEN MANIFEST AND SHIPMENT:

IF WASTE IS HELD FOR DELIVERY ELSEWHERE, SPECIFY THE DESIGNATED TSD FACILITY:

22 Designated TSD Facility Name

23 Signature of Authorized Agent and Title

SO. CALIF. CHEM. CO.

Date Accepted 10/13/82

SEE REVERSE SIDES FOR  
INSTRUCTIONS. PLEASE TYPE  
OR PRINT CLEARLY.

PRESS HARD

70270

# CALIFORNIA HAZARDOUS WASTE MANIFEST

STATE DEPARTMENT OF HEALTH SERVICES  
HAZARDOUS MATERIALS MANAGEMENT SECTION  
744 P STREET, SACRAMENTO, CA 95814

① MANIFEST NUMBER 471 -- 001040

## GENERATOR (GENERATOR MUST COMPLETE)

③ NAME Southern California Chemical Co.

EPA NO. CAD0008488025

ADDRESS 3851 Dice Rd.

CITY, STATE, ZIP CODE Santa Fe Springs, Ca. 90670

PHONE NO. (213) 698-8036

ORDER PLACED BY \_\_\_\_\_ ORDER DATE \_\_\_\_\_

P.O. /  
CONTRACT NO. \_\_\_\_\_

## ③ DESIGNATED TSD FACILITY

(AUTHORIZED TO OPERATE UNDER AN APPROVED STATE OR FEDERAL PROGRAM)

NAME B K K Duno

EPA NO. CAD0067780742

ADDRESS 2210 Azusa Rd.

CITY, STATE, ZIP CODE Covina, Ca.

PHONE NO. \_\_\_\_\_

## ④ ALTERNATE TSD FACILITY

NAME \_\_\_\_\_

EPA NO. \_\_\_\_\_

ADDRESS \_\_\_\_\_

CITY, STATE, ZIP CODE \_\_\_\_\_

PHONE NO. \_\_\_\_\_

⑤ U. S. DOT PROPER SHIPPING NAME	U. S. DOT HAZARD CLASS	UN NA I.D. NO.	WEIGHT OR VOLUME	UNITS	CONTAINERS	NUMBER
WASTE	N/A		4500	gal.	<input checked="" type="checkbox"/> DRUMS	<input type="checkbox"/> BAGS <input type="checkbox"/> CARTONS <input type="checkbox"/> DUMP TRUCK
WASTE					<input type="checkbox"/> TANK TRUCK	<input checked="" type="checkbox"/> OTHER

⑥ WASTE CATEGORY Fluid & Water (37)

⑦ EX. HAZ. WASTE PERMIT NO. N/A

⑧ GENERATING PROCESS \_\_\_\_\_

⑨ LIST COMPONENTS:

A Iron

B Copper

C Chromium

D Other Metals

CONC. RANGE  
UPPER LOWER

UNITS

X %

X %

%

X %

PPM

PPM

PPM

PPM

E Water

F

G

NONHAZARDOUS MATERIAL \_\_\_\_\_ %

CONC. RANGE  
UPPER LOWER

UNITS

%

%

%

%

PPM

PPM

PPM

PPM

⑩ WASTE PROPERTIES:

PH 8.0-9.0

☒ TOXIC

☐ FLAMMABLE

☐ CORROSIVE/IRRITANT

☐ REACTIVE

☐ SENSITIZER

☐ CARCINOGEN/MUTAGEN

⑪ PHYSICAL STATE

☐ SOLID

☐ LIQUID

☐ SLUDGE

☐ SLURRY

☐ GAS

☐ OTHER

⑫ SPECIAL HANDLING INSTRUCTIONS:

☒ GLOVES

☒ GOGGLES

☐ RESPIRATOR

☐ OTHER \_\_\_\_\_

GENERATOR CERTIFICATION: THIS IS TO CERTIFY THAT THE ABOVE NAMED MATERIALS ARE PROPERLY CLASSIFIED, DESCRIBED, PACKAGED, MARKED & LABELED, AND ARE IN PROPER CONDITION FOR TRANSPORTATION ACCORDING TO THE APPLICABLE REGULATIONS OF THE DEPARTMENT OF TRANSPORTATION AND THE EPA.

IN THE EVENT OF A SPILL CONTACT THE NATIONAL  
RESPONSE CENTER, U. S. COAST GUARD 1-800-424-8802.

⑬ G. G. Otterbach, Plant Mgr. 11/18/82

SIGNATURE OF AUTHORIZED AGENT & TITLE

DATE SHIPPED

## TRANSPORTER (HAULER MUST COMPLETE)

⑭ NAME CALIF. CHEMICAL DISPOSAL

EPA NO. CAD98073531 RECEIVED

ADDRESS 12159 LONGWORTH

CITY, STATE, ZIP CODE NORWALK, CA 90650

PHONE NO. (213) 868-1675

JOB NO. 540

UNIT NO. 2-27

⑮ PICK-UP DATE 11-18-82

TIME 3:15

☐ AM

☐ PM

DEC 13 1982

SO CALIF CHEM CO

⑯

SIGNATURE OF AUTHORIZED AGENT & TITLE

## TSD FACILITY (OPERATOR MUST COMPLETE)

⑰ NAME

EPA NO. \_\_\_\_\_

⑱ INDICATE ANY SIGNIFICANT DISCREPANCIES BETWEEN MANIFEST AND SHIPMENT \_\_\_\_\_

⑲ IF WASTE IS HELD FOR DELIVERY ELSEWHERE, SPECIFY THE DESIGNATED TSD FACILITY \_\_\_\_\_

NAME \_\_\_\_\_

NO. \_\_\_\_\_

REVISED 11/80

⑳ QUANTITY (IF MEASURED) (36) (20.36)

㉑ STATE FEE (IF ANY) \$ 21.44

㉒

HANDLING OR DISPOSAL METHOD

☐

SURFACE IMPOUNDMENT

☒

LANDFILL

☐

INJECTION WELL

☐

LAND TREATMENT

☐

TREATMENT (SPECIFY)

☐

RECOVERY OR REUSE

☐

STORAGE TRANSFER

SIGNATURE OF AUTHORIZED AGENT & TITLE

DATE ACCEPTED

Please type or print clearly. Press Hard.

HAZARDOUS MATERIALS MANAGEMENT SECTION  
744 P Street, Sacramento, CA 95814

Number 109 000981

GENERATOR

(GENERATOR MUST COMPLETE)

70270

3 Designated TSD Facility (Authorized to operate under an approved state program or federal program.)

4 Alternate TSD Facility

9:07

2 Name Southern California Chemical

Name BKK Dump

EPA # C A D 0 0 8 4 8 8 0 2 5

EPA # C A D 0 6 7 7 8 6 7 4 9

Address 8851 Dice Rd. Phone 698-8036

Address 2210 Azusa Rd. Phone

City, State, Zip Santa Fe Springs, Ca. 90670

City, State, Zip Covina, Ca.

Address Phone

City, State, Zip

5 U.S. DOT PROPER SHIPPING NAME	N/A	U.S. DOT HAZARD CLASS	N/A	UN/NA ID NO.	None	WEIGHT OR VOLUME	4500	UNITS	gal.	NUMBER OF CONTAINERS	
WASTE		N/A		None		4500		gal.		TYPE:	<input type="checkbox"/> DRUMS <input type="checkbox"/> BAGS <input type="checkbox"/> CARTONS
WASTE											<input checked="" type="checkbox"/> TANK TRUCK <input type="checkbox"/> DUMP TRUCK
											<input type="checkbox"/> OTHER

6 Waste Category Mud & Water (37)

7 Ext. Haz. Waste Permit No. N/A

8 Generating Process Metal Reclaiming

LIST COMPONENTS: CONCENTRATION RANGE UPPER LOWER UNITS

9 A. Iron	25	15	<input checked="" type="checkbox"/> % <input type="checkbox"/> ppm.
B. Copper	5	2	<input checked="" type="checkbox"/> % <input type="checkbox"/> ppm.
C. Chrome	3	.1	<input checked="" type="checkbox"/> % <input type="checkbox"/> ppm.
D. Other Metals	1	.1	<input checked="" type="checkbox"/> % <input type="checkbox"/> ppm.

LIST COMPONENTS: CONCENTRATION RANGE UPPER LOWER UNITS

E. Water	75	60	<input checked="" type="checkbox"/> % <input type="checkbox"/> ppm.
F.			<input type="checkbox"/> % <input type="checkbox"/> ppm.
G.			<input type="checkbox"/> % <input type="checkbox"/> ppm.

Non-Hazardous Material 100 %

10 WASTE PROPERTIES: pH 5.0-9.0 Toxic ☐ Flammable ☒ Corrosive/Irritant ☐ Reactive ☐ Sensitizer ☐ Carcinogen/Mutagen

11 PHYSICAL STATE: ☐ Solid ☐ Liquid ☒ Sludge ☐ Slurry ☐ Gas ☐ Other

12 SPECIAL HANDLING INSTRUCTIONS: ☒ Gloves ☒ Goggles ☐ Respirator ☐ Other

RECEIVED  
MAR 14 1983  
SO. CALIF. CHEM. CO.

GENERATOR CERTIFICATION: This is to certify that the above named materials are properly classified, described, packaged, marked, labeled, and are in proper condition for transportation according to the applicable regulations of the Department of Transportation and EPA.

IN THE EVENT OF A SPILL, CONTACT THE NATIONAL RESPONSE CENTER, U.S. COAST GUARD 1-800-424-8802

13 G. G. Otterbach, Plant Mgr. J. G. Otterbach 2/8/83  
Signature of Authorized Agent and Title Date Shipped

TRANSPORTER

(HAULER MUST COMPLETE)

14 TRANSPORTER NAME NASH SALVAGE INC.

ADDRESS 16211 Placid Drive PHONE (213) 941-5117

CITY, STATE, ZIP Whittier, CA 90604

15 PICK-UP DATE 2-8-83 12854

EPA NO. C A D 9 9 0 8 0 2 9 9 3 Time 4:00 AM ☒ PM

16 Robert McDonald DRIVER 2-8-83  
Signature of Authorized Agent and Title Date

TSD FACILITY

(FACILITY-OPERATOR MUST COMPLETE)

17 NAME BKK 18 QUANTITY (If Measured) 27.02

EPA NO. C A D 0 6 7 7 1 1 1 1 1 1 19 STATE FEE (If Any) \$108.68

PHONE NO.

20 INDICATE ANY SIGNIFICANT DISCREPANCIES BETWEEN MANIFEST AND SHIPMENT:

MANIFEST IS FOR 22 PAIL CONSIDERED HAZARDOUS

IF WASTE IS HELD FOR DELIVERY ELSEWHERE, SPECIFY THE DESIGNATED TSD FACILITY:

22 Designated TSD Facility Name

23 [Signature] Signature of Authorized Agent and Title

21 HANDLING OR DISPOSAL METHOD:

☐ Surface Impoundment ☒ Landfill  
☐ Injection Well ☐ Land Treatment  
☐ Treatment (Specify)  
☐ Recovery or Re-use ☐ Storage/Transfer  
☐ Recycle

EPA NO. 2/8/83  
Date Accepted

UNIFORM HAZARDOUS WASTE MANIFEST

(Please print or type with ELITE type (12 characters per inch).)

STATE ID NUMBER **8252297**

GENERATOR NAME AND MAILING ADDRESS

**Southern California Chemical Co., Inc.**  
**8851 Dice Road., Santa Fe Springs, Ca. 90670**

AREA CODE/PHONE NUMBER **(213) 698-8036**

MANIFEST DOCUMENT NUMBER

EPA ID NUMBER

**CAD00848802502885**

TRANSPORTER NO. 1

**Nash Salvage Inc., 16211 Placid Drive**  
**Whittier, Ca. 90604**

VEH./CONTAINER NO.

EPA ID NUMBER

**00003847 CAD990802993**

TRANSPORTER NO. 2/ALTERNATE TSD FACILITY

EPA ID NUMBER

TREATMENT, STORAGE, OR DISPOSAL (TSD) FACILITY

**BKK LDF**  
**2210 Azusa Rd., West Covina, Ca.**

AREA CODE/PHONE NUMBER **(213) 965-0916**

EPA ID NUMBER

**CAD067786749**

PROPER U.S. D.O.T. SHIPPING NAME AND HAZARD CLASS

UN/NA  
NUMBER

TOTAL  
QUANTITY

UNIT  
WT/VOL

CONTAINER  
NO. TYPE

WASTE  
CAT. NO.

**Unspecified Sludge Waste**

**N/A**

**4700**

**G**

**001 TC**

**491**

COMPONENTS

CONC.  
UPPER

RANGE  
LOWER

UNITS  
% ppm

**Iron**  
**Copper**

**25**  
**5**

**15**  
**2**

**X**  
**X**

**Chrome**  
**Other Metals**

**3**  
**1**

**.1**  
**.1**

**X**  
**X**

**Water**

**75**

**60**

**X**

SPECIAL HANDLING INSTRUCTIONS

**Gloves, Goggles**

This is to certify that the above-named materials are properly classified, described, packaged, marked and labeled, and are in proper condition for transportation according to the applicable regulations of the Department of Transportation and the EPA.

**G. G. Otterbach, Plant Manager**

PRINTED OR TYPED FULL NAME AND SIGNATURE

MO. DAY YR.

**04 12 83**

☐ CHECK IF CONTINUATION SHEET IS USED. NUMBER OF CONTINUATION SHEETS

TRANSPORTER 1 ACKNOWLEDGEMENT OF RECEIPT OF ABOVE MATERIALS

DATE REC'D & ACCEPTED

**Nash Salvage Driver**

PRINTED OR TYPED FULL NAME AND SIGNATURE

MO. DAY YR.

**04 12 83**

TRANSPORTER 2 ACKNOWLEDGEMENT OF RECEIPT OF ABOVE MATERIALS

DATE REC'D & ACCEPTED

PRINTED OR TYPED FULL NAME AND SIGNATURE

MO. DAY YR.

**04 12 83**

DISCREPANCY INDICATION SPACE

Facility owner or operator: Certification of receipt of hazardous material covered by this manifest except as noted in the discrepancy indication space above. Note: TSD must complete waste number. See instructions.

DATE REC'D & ACCEPTED

PRINTED OR TYPED FULL NAME AND SIGNATURE

EPA ID NUMBER

MO. DAY YR.

**04 12 83**

Original—White—Disposer send to DHS; Green—Hauler; Yellow—Disposer; Pink—Generator

UNIFORM HAZARDOUS WASTE MANIFEST

Please print or type with ELITE type (12 characters per inch).

70270

STATE ID NUMBER 83040102

GENERATOR NAME AND MAILING ADDRESS

Southern California Chemical Co., Inc.  
8251 Dice Road, Santa Fe Springs, Ca. 90670  
(213) 658-8036

MANIFEST DOCUMENT NUMBER

EPA ID NUMBER

AREA CODE/PHONE NUMBER

TRANSPORTER NO. 1

Nash Salvage, Inc., 16211 Flacid Drive  
Whittier, Ca. 90604

VEH./CONTAINER NO.

EPA ID NUMBER

TRANSPORTER NO. 2/ALTERNATE TSD FACILITY

VEH./CONTAINER NO.

EPA ID NUMBER

TREATMENT, STORAGE, OR DISPOSAL (TSD) FACILITY

BKK LDF  
2210 Azusa Rd., West Covina, Ca.  
(213) 965-0916

AREA CODE/PHONE NUMBER

EPA ID NUMBER

PROPER U.S. D.O.T. SHIPPING NAME AND HAZARD CLASS

UN/NA  
NUMBER

TOTAL  
QUANTITY

UNIT  
WT/VOL

CONTAINER  
NO.

WASTE  
CAT NO.

Unspecified Sludge Waste (Non-Halogenated)

NONHAZ

145000

G

001

TIC

491

COMPONENTS

CONC. RANGE

UPPER

LOWER

UNITS

% P

Iron

25

15

X

Copper

5

2

X

Chrome

3

.1

X

Other Metals

1

.1

X

Water

75

60

X

SPECIAL HANDLING INSTRUCTIONS

Gloves, Goggles

This is to certify that the above-named wastes are properly classified, described, packaged, marked and labeled, and are in proper condition for transportation according to the applicable requirements of the Department of Transportation and the EPA.

G. G. Otterbach, Plant Manager

Printed or typed full name and signature

MO.

DAY

YR

07

28

81

☐ Check if continuation sheet is used. Number of continuation sheets

TRANSPORTER 1 ACKNOWLEDGEMENT OF RECEIPT OF ABOVE WASTES

Nash Salvage Driver

Printed or typed full name and signature

DATE  
REC'D  
&  
ACCEPTED

MO.

DAY

YF

TRANSPORTER 2 ACKNOWLEDGEMENT OF RECEIPT OF ABOVE WASTES

Printed or typed full name and signature

DATE  
REC'D  
&  
ACCEPTED

MO.

DAY

YF

DISCREPANCY INDICATION SPACE

Facility owner or operator: Certification of receipt of hazardous waste covered by this manifest except as noted in the discrepancy indication space above. Note: TSDF must complete waste number. See instructions.

Printed or typed full name and signature

EPA ID NUMBER

MO.

DAY

YF

TSDF RETAINS



STATE ID NUMBER **8 3040193**

Print or type with ELITE type (12 characters per inch).

GENERATOR NAME AND MAILING ADDRESS <b>Southern California Chemical Co., Inc. 8851 Dice Road, Santa Fe Springs, Ca. 90670 (213) 693-3036</b>		MANIFEST DOCUMENT NUMBER <b>70270</b>				
AREA CODE/PHONE NUMBER <b>01701010134121012510101013</b>		EPA ID NUMBER				
TRANSPORTER NO. 1 <b>Nash Salvage, Inc., 16211 Placid Drive Whittier, Ca. 90604</b>		VEH./CONTAINER NO. <b>03740065</b>				
TRANSPORTER NO. 2/ALTERNATE TSD FACILITY		EPA ID NUMBER				
TREATMENT, STORAGE, OR DISPOSAL (TSD) FACILITY <b>BKK LDF 2210 Azusa Rd., West Covina, Ca. (213) 965-0916</b>		EPA ID NUMBER				
AREA CODE/PHONE NUMBER <b>0170101617121617410</b>		EPA ID NUMBER				
PROPER U.S. D.O.T. SHIPPING NAME AND HAZARD CLASS	UN/NA NUMBER	TOTAL QUANTITY	UNIT WT/VOL	CONTAINER NO.	WASTE CAT NO.	DISP. METH.
<b>Unspecified Sludge Waste (Non-Halogenated)</b>	<b>10101011</b>	<b>14151010</b>	<b>6</b>	<b>01011</b>	<b>1011</b>	<b>03</b>
COMPONENTS			CONC. RANGE		UNITS	
			UPPER	LOWER	%	PPM
<b>Iron</b>			<b>25</b>	<b>15</b>	<b>X</b>	
<b>Copper</b>			<b>5</b>	<b>2</b>	<b>X</b>	
<b>Zinc</b>			<b>1</b>	<b>.2</b>	<b>X</b>	
<b>Water</b>			<b>75</b>	<b>50</b>	<b>X</b>	
<b>RECEIVED</b>						
<b>NOV 8 1983</b>						
<b>SO. CALIF. CHEM. CO.</b>						
This is to certify that the above-named wastes are properly classified, described, packaged, marked and labeled, and are in proper condition for transportation according to the applicable requirements of the Department of Transportation and the EPA.						
G. G. Otterbach, Plant Manager						
Printed or typed full name and signature						
<input type="checkbox"/> Check if continuation sheet is used. Number of continuation sheets						
TRANSPORTER 1 ACKNOWLEDGEMENT OF RECEIPT OF ABOVE WASTES						
Nash Salvage Driver <b>Devis Kissen</b>						
Printed or typed full name and signature						
TRANSPORTER 2 ACKNOWLEDGEMENT OF RECEIPT OF ABOVE WASTES						
Printed or typed full name and signature						
DISCREPANCY INDICATION SPACE						
Facility owner or operator: Certification of receipt of hazardous waste covered by this manifest except as noted in the discrepancy indication space above. Note: TSD must complete waste number. See instructions.						
Printed or typed full name and signature						
DATE RECEIVED & ACCEPTED						
MO. DAY YR.						
<b>10 06 83</b>						
TSD SENDS THIS COPY TO GENERATOR WITHIN 15 DAYS						



Please print or type with ELITE type (12 characters per inch).

STATE ID NUMBER 83587061

GENERATOR NAME AND MAILING ADDRESS

Southern California Chemical Co.  
8851 Dice Road  
Santa Fe Springs, CA 90670

AREA CODE/PHONE NUMBER (213) 639-8035

MANIFEST DOCUMENT NUMBER

EPA ID NUMBER

TRANSPORTER NO. 1

189 Nash Salvage Inc.  
16211 Placid Drive  
Whittier, CA 90604  
(213) 641-5117

VEH./CONTAINER NO. 000486 EPA ID NUMBER

TRANSPORTER NO. 2/ALTERNATE TSD FACILITY

Return to Generator

VEH./CONTAINER NO. CAD9 EPA ID NUMBER 299

TREATMENT, STORAGE, OR DISPOSAL (TSD) FACILITY

Environmental Protection Corporation  
Westside Disposal  
Highway 33 Fellows, CA. (805)327-9681

AREA CODE/PHONE NUMBER

EPA ID NUMBER

PROPER U.S. D.O.T. SHIPPING NAME AND HAZARD CLASS

UN/NA  
NUMBER

TOTAL  
QUANTITY

UNIT  
WT/VOL

CONTAINER  
NO.

WASTE  
CAT. NO.

DI.  
ME

R.O.  
Hazardous Waste, Liquid, H.O.S. ORN-E

NA 9199

4000 G

001CT1320

COMPONENTS

CONC. RANGE  
UPPER LOWER

UNITS  
% PPM

Iron  
Copper

25

15

X

Zinc

15

2

X

Chrome, Trivalent

1

0.2

X

Salt

2

0.5

X

Ammonium Sulfate

5

2

X

Caustic Soda

5

2

X

Water

55

45

X

SPECIAL HANDLING INSTRUCTIONS

Gloves & Goggles Liquid pH = 4

This is to certify that the above-named wastes are properly classified, described, packaged, marked and labeled, and are in proper condition for transportation according to the applicable requirements of the Department of Transportation and the EPA.

G. G. Otterbach, Plant Manager

Printed or typed full name and signature

MO.

DAY

YR.

03

02

84

☐ Check if continuation sheet is used. Number of continuation sheets

TRANSPORTER 1 ACKNOWLEDGEMENT OF RECEIPT OF ABOVE WASTES

Printed or typed full name and signature

TRANSPORTER 2 ACKNOWLEDGEMENT OF RECEIPT OF ABOVE WASTES

Printed or typed full name and signature

DISCREPANCY INDICATION SPACE

Facility owner or operator: Certification of receipt of hazardous waste covered by this manifest except as noted in the discrepancy indication space above. Note: TSDF must complete waste number. See instructions.

DATE RECEIVED & ACCEPTED

EPA ID NUMBER

MO.

DAY

YR.

Printed or typed full name and signature

GENERATOR RETAINS

83-87967

CONTROL DIVISION

## UNIFORM HAZARDOUS WASTE MANIFEST

FORM NO. DHS-8022A 3-84

95814

Print type with ELITE type (12 characters per inch).

STATE ID NUMBER

WO 152  
83611314

GENERATOR NAME AND MAILING ADDRESS

Southern California Chemical Co.  
8851 Dice Road  
Santa Fe Springs, CA 90670

MANIFEST DOCUMENT NUMBER

EPA ID NUMBER

AREA CODE/PHONE NUMBER

(213) 698-8036

C A D 0 0 3 4 8 2 0 2 5

TRANSPORTER NO. 1 NAME AND MAILING ADDRESS

189 Nash Salvage Inc.  
16211 Placid Drive  
Whittier, CA 90604  
(213) 941-5117

VEH/CONTAINER NO.

EPA ID NUMBER

TRANSPORTER NO. 2/ALTERNATE TSD FACILITY

VEH/CONTAINER NO.

EPA ID NUMBER

Return To Generator

AREA CODE/PHONE NUMBER

TREATMENT, STORAGE, OR DISPOSAL (TSD) FACILITY

Environmental Protection Corporation  
Westside Disposal  
Highway 33  
Fellow, CA

AREA CODE/PHONE NUMBER

(805) 327-9581

C A D 0 0 3 4 8 2 0 2 5

PROPER U.S. D.O.T. SHIPPING NAME AND HAZARD CLASS

UN/NA  
NUMBERTOTAL  
QUANTITYUNIT  
WT/VOLCONTAINER  
NOWASTE  
CAT. NODISP.  
METH

Hazardous Waste, Liquid, N.O.S. ORM-E

N/A 9189

4000

G

001

CT

13203

COMPONENTS

CONC RANGE  
UPPER LOWERUNITS  
% PPM

Iron

25

15

X

Copper

15

2

X

Zinc

1

0.2

X

Chromium, Trivalent

2

0.5

X

Salt

5

2

X

Ammonium Sulfate

5

2

X

Caustic Soda

5

2

X

Water

55

45

X

SPECIAL HANDLING INSTRUCTIONS

Gloves &amp; Goggles

Liquid pH

This is to certify that the above-named wastes are properly classified, described, packaged, marked and labeled, and are in proper condition for transportation according to the applicable requirements of the Department of Transportation and the EPA.

G. G. Otterbach - Plant Manager

Printed or typed full name and signature

MO.	DAY	YR
11	20	84

☐ Check if continuation sheet is used. Number of continuation sheets

TRANSPORTER 1 ACKNOWLEDGEMENT OF RECEIPT OF ABOVE WASTES

Printed or typed full name and signature

DATE  
REC'D  
&  
ACCEPTED

MO.	DAY	YR
11	21	84

TRANSPORTER 2 ACKNOWLEDGEMENT OF RECEIPT OF ABOVE WASTES

Printed or typed full name and signature

DATE  
REC'D  
&  
ACCEPTED

MO.	DAY	YR

DISCREPANCY INDICATION SPACE

Facility owner or operator: Certification of receipt of hazardous waste covered by this manifest except as noted in the discrepancy indication space above. Note: TSD must complete waste number. See instructions.

DATE RECEIVED &amp; ACCEPTED

EPA ID NUMBER

MO.	DAY	YR

Printed or typed full name and signature

GENERATOR RETAINS

Please print or type. (Form designed for use on elite (12-pitch) typewriter.)

50152

<b>UNIFORM HAZARDOUS WASTE MANIFEST</b>		1. Generator's US EPA ID No. <b>CAD008488025</b>		Manifest Document No. <b>1</b>		2. Page 1 of		Information in the shaded areas is not required by Federal law.			
3. Generator's Name and Mailing Address <b>Southern California Chemical Co. Inc. 8351 Dice Road, Santa Fe Springs, CA 90670</b>						A.State Manifest Document Number <b>84152816</b>					
4. Generator's Phone (212) <b>698-8036</b>						B.State Generator's ID <b>CAD008488025</b>					
5. Transporter 1 Company Name <b>Nash Salvage Inc</b>						C.State Transporter's ID <b>53319</b>					
6. US EPA ID Number <b>CAD998902993</b>						D.Transporter's Phone <b>(213) 941-5117</b>					
7. Transporter 2 Company Name						E.State Transporter's ID					
8. US EPA ID Number						F.Transporter's Phone					
9. Designated Facility Name and Site Address <b>Environmental Protection Corporation Westside Disposal, Hwy. 33, Fellows, CA (805) 327-9681</b>						G.State Facility's ID <b>CAT 080010283</b>					
10. US EPA ID Number <b>CAT 080010283</b>						H.Facility's Phone <b>805-768-4806</b>					
11. US DOT Description (Including Proper Shipping Name, Hazard Class, and ID Number)						12. Containers		13. Total Quantity		14. Unit	
						No.	Type	Wt/Vol		L. Waste No.	
a. <b>RQ Hazardous Waste, Liquid, N.O.S. ORM-E NA9189</b>						<b>001</b>	<b>CT</b>	<b>4500</b>	<b>G</b>	<b>132</b>	
b.											
c.											
d.											
J. Additional Descriptions for Materials Listed Above						K. Handling Codes for Wastes Listed Above					
<b>Chrome #3 Approx. 3% Liquid ph= above 2</b> <b>Copper 5%</b> <b>Nickel .05%</b> <b>Iron 10%</b>						<b>04</b>					
15. Special Handling Instructions and Additional Information  <b>Gloves &amp; Goggles</b>											
16. GENERATOR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by proper shipping name and are classified, packed, marked, and labeled, and are in all respects in proper condition for transport by highway according to applicable international and national governmental regulations.											
Printed/Typed Name <b>G. G. Otterbach</b>						Signature <i>G. G. Otterbach</i>			Date <b>8-1-85</b>		
17. Transporter 1 Acknowledgement of Receipt of Materials						Printed/Typed Name <i>Robert McDaniel</i>			Signature <i>Robert McDaniel</i>		
18. Transporter 2 Acknowledgement or Receipt of Materials						Printed/Typed Name <b>RECEIVED</b>			Date <b>8-1-85</b>		
19. Discrepancy Indication Space						<b>JAN 30 1985</b> <b>SO. CALIF. CHEM. CO.</b>					
20. Facility Owner or Operator: Certification of receipt of hazardous materials covered by this manifest except as noted in Item 19.						Printed/Typed Name <b>JOHANNA HEVEY</b>			Signature <i>Johanna Hevey</i>		
									Date <b>1-11-85</b>		

Yellow: GENERATOR RETAINS

Please print or type. (Form designed for use on elite (12-pitch) typewriter.)

W0152

<b>UNIFORM HAZARDOUS WASTE MANIFEST</b>		1. Generator's US EPA ID No. <b>CAD008488025</b>		Manifest Document No. <b>1</b>		2. Page 1 of <b>1</b>		Information in the shaded areas is not required by Federal law.							
3. Generator's Name and Mailing Address <b>Southern California Chemical Co., Inc. 8851 Dice Road, Santa Fe Springs, CA 90670</b>						A. State Manifest Document Number <b>84536001 W0152</b>									
4. Generator's Phone (213) <b>698-8036</b>						B. State Generator's ID <b>CAD008488025</b>									
5. Transporter 1 Company Name <b>189 Nash Salvage Inc.</b>						C. State Transporter's ID <b>53319</b>									
6. US EPA ID Number <b>CAD998902993</b>						D. Transporter's Phone <b>941-5117</b>									
7. Transporter 2 Company Name						E. State Transporter's ID									
8. US EPA ID Number						F. Transporter's Phone									
9. Designated Facility Name and Site Address <b>Environmental Protection Corporation Westside Disposal, Hwy. 33, Fellows, CA (805) 327-9681</b>						G. State Facility's ID <b>CA T040010243</b>									
10. US EPA ID Number <b>CAT080010283</b>						H. Facility's Phone <b>405-7644506</b>									
11. US DOT Description (Including Proper Shipping Name, Hazard Class, and ID Number)  <b>a. RQ Hazardous Waste, Liquid, N.O.S. ORM-E NA9189</b>  <b>b.</b>  <b>c.</b>  <b>d.</b>						12. Containers		13. Total		14. Unit		15. Waste No.			
						No.		Type		Quantity		Wt/Vol			
						<b>001</b>		<b>CT</b>		<b>4500</b>		<b>G</b>		<b>132</b>	
J. Additional Descriptions for Materials Listed Above <b>Chrome +3 Approx 3% Liquid ph= alone</b> <b>Copper 5%</b> <b>Nickel .05%</b> <b>Iron 10%</b>						K. Handling Codes for Wastes Listed Above  <b>04</b>									
15. Special Handling Instructions and Additional Information  <b>Gloves &amp; Goggles</b>															
16. GENERATOR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by proper shipping name and are classified, packed, marked, and labeled, and are in all respects in proper condition for transport by highway according to applicable international and national governmental regulations.															
Printed/Typed Name <b>G. G. Otterbach</b>						Signature <i>G. G. Otterbach</i>		Date <b>01/08/85</b>							
17. Transporter 1 Acknowledgement of Receipt of Materials						Signature <i>F. E. Osburn</i>		Date <b>01/08/85</b>							
Printed/Typed Name <b>FRED E. OSBURN</b>						Signature <i>F. E. Osburn</i>		Date <b>01/08/85</b>							
18. Transporter 2 Acknowledgement or Receipt of Materials						Signature <b>RECEIVED</b>		Date <b>01/08/85</b>							
Printed/Typed Name						Signature		Date							
19. Discrepancy Indication Space						JAN 30 1985		D-11							
						SO. CALIF. CHEM. CO.									
20. Facility Owner or Operator: Certification of receipt of hazardous materials covered by this manifest except as noted in Item 19.															
Printed/Typed Name <b>ROLAND FATEWOOD</b>						Signature <i>Roland Fatewood</i>		Date <b>1/19/85</b>							



W0152 H

Please print or type. (Form designed for use on elite (12-pitch) typewriter.)

UNIFORM HAZARDOUS WASTE MANIFEST		1. Generator's US EPA ID No. C A D 0 0 8 4 8 8 0 2 5	Manifest Document No.	2. Page 1 of	Information in the shaded areas is not required by Federal law.
3. Generator's Name and Mailing Address Southern California Chemical Co., Inc. 8851 Dice Road, Santa Fe Springs, CA. 90670			A. State Manifest Document Number 84153102		
4. Generator's Phone (213) 698-8036			B. State Generator's ID C A D 0 0 8 4 8 8 0 2 5		
5. Transporter 1 Company Name Nash Salvage Inc.			C. State Transporter's ID 5 3 3 1 3		
6. US EPA ID Number C A D 0 0 8 0 2 9 9 3			D. Transporter's Phone 213/941-5117		
7. Transporter 2 Company Name			E. State Transporter's ID		
8. US EPA ID Number			F. Transporter's Phone		
9. Designated Facility Name and Site Address Environmental Protection Corporation Westside Disposal, Hwy 33, Fellows, CA (805) 327-9631			G. State Facility's ID C A D 0 0 1 0 2 8 3		
10. US EPA ID Number C A D 0 0 1 0 2 8 3			H. Facility's Phone		
11. US DOT Description (Including Proper Shipping Name, Hazard Class, and ID Number)		12. Containers No.	13. Total Quantity	14. Unit Wt/Vol	15. Waste No.
a. RQ Hazardous Waste, Liquid, N.O.S. NA9189 Dot E7476		001	TT	4500	G 132
b.					
c.					
d.					
J. Additional Descriptions for Materials Listed Above Chrom 3 Approx 3% Liquid pH = 11.5 above 2 Copper 3% Nickel 0.5% Iron 2% 01 fo			K. Handling Codes for Wastes Listed Above 04		
15. Special Handling Instructions and Additional Information Gloves and Goggles W0 152					
16. GENERATOR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by proper shipping name and are classified, packed, marked, and labeled, and are in all respects in proper condition for transport by highway according to applicable international and national governmental regulations.					
Printed/Typed Name G. Otterbach		Signature <i>G. Otterbach</i>		Date 6/12/85	
17. Transporter 1 Acknowledgement of Receipt of Materials		Signature <i>Fred E. Osh</i>		Date 6/12/85	
Printed/Typed Name		Signature <i>Fred E. Osh</i>		Date 6/12/85	
18. Transporter 2 Acknowledgement or Receipt of Materials		Signature <i>RECEIVED</i>		Date MAY 13 1985	
Printed/Typed Name		Signature		Date SO. CALIF. CHEM. CO. 12-12	
19. Discrepancy Indication Space					
20. Facility Owner or Operator: Certification of receipt of hazardous materials covered by this manifest except as noted in item 19.					
Printed/Typed Name Sivan E Patzor		Signature <i>Sivan E Patzor</i>		Date 6/12/85	

Yellow: TSDF SENDS THIS COPY TO GENERATOR WITHIN 30 DAYS

pH 4-7 W0152

EPC# 62127

Please print or type. (Form designed for use on elite (12-pitch) typewriter.)

WD 157

<b>UNIFORM HAZARDOUS WASTE MANIFEST</b>		1. Generator's US EPA ID No. <b>C A D 0 0 8 4 8 8 0 2 5</b>		Manifest Document No.		2. Page 1 of		Information in the shaded areas is not required by Federal law.					
3. Generator's Name and Mailing Address <b>Southern California Chemical Co., Inc. 8851 Dice Road, Santa Fe Springs, CA 90670</b>						A. State Manifest Document Number <b>84152948</b>							
4. Generator's Phone ( 213 ) 698-8036						B. State Generator's ID							
5. Transporter 1 Company Name <b>Nash Salvage Inc.</b>			6. US EPA ID Number <b>ICAD 99080299</b>			C. State Transporter's ID <b>532/3</b>							
7. Transporter 2 Company Name			8. US EPA ID Number			D. Transporter's Phone <b>213/941-5117</b>							
9. Designated Facility Name and Site Address <b>Environmental Protection Corporation Westside Disposal, Hwy 33, Fellows, CA (805) 327-9681</b>			10. US EPA ID Number <b>ICAD 080010283</b>			E. State Transporter's ID							
						F. Transporter's Phone							
						G. State Facility's ID <b>CA080010283</b>							
						H. Facility's Phone							
11. US DOT Description (Including Proper Shipping Name, Hazard Class, and ID Number) <b>a. Hazardous Waste, Liquid, N.O.S. NA9189 DOT 7476 / ORMC</b>						12. Containers		13. Total Quantity		14. Unit		1. Waste No.	
						No. Type		Quantity		Unit		Waste No.	
						0 0 1 TT		4500		G		132	
b.													
c.													
d.													
J. Additional Descriptions for Materials Listed Above <b>Chrome +3 Approx. 3% Liquid pH=above 2 Copper " 3% Nickel " .01% Iron " 2%</b>						K. Handling Codes for Wastes Listed Above <b>04</b> <b>Casmalia Resources NTU Road, Casmalia, CA 93429</b>							
15. Special Handling Instructions and Additional Information <b>Gloves and Goggles WD 152</b>										<b>RECEIVED</b> <b>JUN 13 1985</b> <b>SO. CALIF. CHEM. CO.</b>			
16. GENERATOR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by proper shipping name and are classified, packed, marked, and labeled, and are in all respects in proper condition for transport by highway according to applicable international and national governmental regulations.													
Printed/Typed Name <b>G. Otterbach</b>						Signature <i>[Signature]</i>		Date <b>05/28/85</b>					
17. Transporter 1 Acknowledgement of Receipt of Materials						Printed/Typed Name <b>Robert McDonald</b>		Signature <i>[Signature]</i>		Date <b>05/28/85</b>			
18. Transporter 2 Acknowledgement or Receipt of Materials						Printed/Typed Name		Signature		Date			
19. Discrepancy Indication Space													
20. Facility Owner or Operator: Certification of receipt of hazardous materials covered by this manifest except as noted in Item 19.						Printed/Typed Name <b>Susan S Patzov</b>		Signature <i>[Signature]</i>		Date <b>05/28/85</b>			

Yellow: TSDF SENDS THIS COPY TO GENERATOR WITHIN 30 DAYS

Please print or type. (Form designed for use on elite (12-pitch) typewriter.)

E.P.C 0100W

UNIFORM HAZARDOUS WASTE MANIFEST		1. Generator's US EPA ID No.	Manifest Document No.	2. Page 1 of	Information in the shaded area is not required by Federal law.
3. Generator's Name and Mailing Address		4. Generator's Phone (213) 698-8036		A. State Manifest Document Number 84152949	
Southern California Chemical Co., Inc. 8851 Dice Rd. Santa Fe Springs, CA 90670		5. Transporter 1 Company Name Nash Salvage, Inc.		B. State Generator's ID CAD 008488025 6362	
6. US EPA ID Number		7. Transporter 2 Company Name		C. State Transporter's ID	
C.A.D. 9908029		8. US EPA ID Number		D. Transporter's Phone 213/941-5111	
9. Designated Facility Name and Site Address		10. US EPA ID Number		E. State Transporter's ID	
Environmental Protection Corp. Westside Disposal, Highway 33, Fellows, CA Approval No. 0100W		I.C.A.T. 080010283		F. Transporter's Phone	
11. US DOT Description (Including Proper Shipping Name, Hazard Class, and ID Number)		12. Containers		13. Total Quantity	
a. Hazardous Waste, Liquid, N.O.S. ORM-E NA9189 DOT # 8822		No. Type		Unit	
		001 ET		3800 G	
b.					
c.					
d.					
J. Additional Descriptions for Materials Listed Above		K. Handling Codes for Wastes Listed Above			
Chrome +3 Approx 3% Liquid pH= Above 4 Copper " 3% Nickel " 0.5% Iron " 3%		09			
15. Special Handling Instructions and Additional Information		Alternate TSD: Casmalia Resources NTU Road, Casmalia, CA 934 805/937-8449 CAD020748125 WAN 0165			
Gloves and Goggles					
16. GENERATOR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by proper shipping name and are classified, packed, marked, and labeled, and are in all respects in proper condition for transport by highway according to applicable international and national governmental regulations.					
Printed/Typed Name Southern California Chemical Co by: G. Otterbach		Signature		Date	
		G. Otterbach		09/15/85	
17. Transporter 1 Acknowledgement of Receipt of Materials		Signature		Date	
Printed/Typed Name ROBERT D McDONALD		ROBERT McDONALD		08/15/85	
18. Transporter 2 Acknowledgement or Receipt of Materials		Signature		Date	
Printed/Typed Name				Month Day	
				11	
19. Discrepancy Indication Space					
SEP 18 1985 SO. CALIF. CHEM. CO. D-14					
20. Facility Owner or Operator: Certification of receipt of hazardous materials covered by this manifest except as noted in item 19.					
Printed/Typed Name		Signature		Date	
ROLAND KATEWOOD		Roland Katewood		08/15/85	

Yellow: TSD/ SENDS THIS COPY TO GENERATOR WITHIN 30 DAYS

H-9.1 TW 0.2 Field WW3 EPC# 45816

J. H. KLEINFELDER & ASSOCIATES

APPENDIX E



LAB REQUEST

Date Submitted: 2-5-85 Lab No. 0411

From: G. Otterbach Representing: \_\_\_\_\_

Sample Source: Mudge from the pond #1  
at SFS plant. (SCC-CP).

Sample Description: \_\_\_\_\_

Analysis Required: \_\_\_\_\_

Sample Identification  
 (Lab No.)

Analysis

	Sample "as is"	Dried sample.
Cu	2.9%	12.3%
Fe	2.06%	8.77%
Zn	0.9%	3.67%
Cr	0.54%	2.24%
Ni	0.026%	0.12%
Pb	0.029%	0.15%
Cd	nil	0.03%
Na	2.91%	12.65%
Residue	1.35%	4.7%
		Moisture = 76.5%

Date Completed: 2-6-85 By: Sonya Shastana

SOC-79  
 9/14/76

LAB REQUEST

Date Submitted: 10-09-84 Lab No. \_\_\_\_\_

From: C. Otterbach Representing: \_\_\_\_\_

Sample Source: \_\_\_\_\_

Sample Description: Sludge from Pond

Analysis Required: Cu, Ni, Fe, Cr, Zn

Sample Identification  
(Lab No.)

Analysis

	<u>(10-09-84)</u>	<u>(10-10-84)</u> Very Wet
Cu =	7.2%	3.6%
Fe =	18.7%	9.0%
Zn =	1.64%	0.81%
Cr =	0.87%	0.46%
Ni =	nil	nil

Date Completed: 10-09-84 By: Sonja

SOC-79  
9/14/76

LAB REQUESTDate submitted 2-19-85 Lab No. 0539From B. Otterbach.Sample source Sludge sample fromPond #1 after Cr-treatment.

Sample description \_\_\_\_\_

Analysis required \_\_\_\_\_

Sample Identification  
(Lab No.)

Analysis

Cu = 3.7%

Fe = 1.6%

Total Cr = 3.8%

Zn = 0.31%

Ni = 0.016%

Pb = 0.008%

Cd = nil

Na = 3.1%

Moisture = 69.23%

Date completed 2-20-85 By Souja Shortino